

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

RECEIVED
JUN 25 1970
STATE ENGINEER
SALEM, OREGON

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

6-5213

State Well No.

State Permit No.

34/19-21a

6-4826?

(1) OWNER:

Name Harold BuffeornAddress 1698 Iler St. Salem, Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

4" Diam. from 0' ft. to 357' ft. Gage 1/4"

10" Diam. from 347' ft. to 470' ft. Gage 3/16"

" Diam. from " ft. to " ft. Gage "

(6) PERFORATIONS:

Perforated? ☐ Yes ☐ No.

of perforator used

Size of perforations in. by in.

(2) 1/4 to 3/8" - 26" perforations from 35' ft. to 55' ft.

Slots/ft. perforations from 134' ft. to 139' ft.

Torch Perfs. perforations from 195' ft. to 296' ft.

perforations from 327' ft. to 360' ft.

(4) 1/8 x 5" Slots/ft. perforations from 347' ft. to 470' ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from " ft. to " ft.

Diam. Slot size Set from " ft. to " ft.

(8) WATER LEVEL: Completed well.

Static level 31 ft. below land surface Date 6/14/70

Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static levelWas a pump test made? ☒ Yes ☐ No If yes, by whom? Rogers Mach.

Yield: 700 gal./min. with 300' ft. drawdown after 96 hrs.

" 269' " " "

Bailer test gal./min. with " ft. drawdown after " hrs.

Artesian flow g.p.m. Date

Temperature of water 56° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Gravel & Cement

Depth of seal 30' ft.

Diameter of well bore to bottom of seal 20" in.

Were any loose strata cemented off? ☒ Yes ☐ No Depth 5' to 20'Was a drive shoe used? ☐ Yes ☒ NoDid any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/4"

Gravel placed from 30' ft. to 357' ft.

(11) LOCATION OF WELL:

County Lake

Driller's well number

Paisley #1

1/4 NE 1/4 Section 21 T. 34 S. R. 19 E. W.M.

Bearing and distance from section or subdivision corner

1320' S. and 1320' W. from NE corner
of Sec 21, T 34 S, R 19 E W.M.

(12) WELL LOG:

Diameter of well below casing

Depth drilled 470' ft. Depth of completed well 470' ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top Soil	0	5	
Gravel	5	20	
Clay	20	32	
Sand + Gravel	32	55	
Gravel + Brks Rock	55	85	
Course Gravel + Rock	85	134	
Sand	134	139	
Gravel + Sand	139	195	
Sand + Gravel	195	296	
Hd. Sand + Gravel	296	327	
Loose sand + Gravel	327	462	
Course Gravel + Rock	462	470	

Work started 4/23/70 19 Completed 6/8/70 19

Date well drilling machine moved off of well 6/8/70 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials
used and information reported above are true to my best
knowledge and belief.

[Signed] Al Ellsworth Date 6/18, 19 70

(Drilling Machine Operator)

Drilling Machine Operator's License No. 667

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

NAME Land, Lake, Livestock Inc.

(Person, firm or corporation)

(Type or print)

Address 1698 Iler St So, Salem Ore[Signed] Donald Buffeorn

(Water Well Contractor)

Contractor's License No. 531 Date 6/22/70 19

(USE ADDITIONAL SHEETS IF NECESSARY)