

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

NOV 2 1976

State Well No.

WATER RESOURCES DEPT.

State Permit No.

WIDL 156688

(1) OWNER:

Name Bar-C RanchAddress Paisley, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Cable ☐ Dug ☐
Driven ☐ Jetted ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
12" Diam. from 0 ft. to 320 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.Type of perforator used torchSize of perforations 3/16 in. by 6 in.
2240 perforations from 40 ft. to 320 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static levelWas a pump test made? ☒ Yes ☐ No If yes, by whom? driller300 gal./min. with 110 ft. drawdown after 24 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 54 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used cementWell sealed from land surface to 20 ft.Diameter of well bore to bottom of seal 30 in.Diameter of well bore below seal 22 in.Number of sacks of cement used in well seal 26 sacks

Number of sacks of bentonite used in well seal sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/8Gravel placed from 20 ft. to 320 ft.

(10) LOCATION OF WELL:

County Lake Driller's well numberNW $\frac{1}{4}$ SW $\frac{3}{4}$ Section 21 T. 34 R. 19 W.M.

Bearing and distance from section or subdivision corner

6 1/2 miles southeast of Paisley, OR34826 HWY 31, 42.60477917, -120.47926866

(11) WATER LEVEL: Completed well.

Depth at which water was first found 72 ft.Static level 50 ft. below land surface. Date 11/1/76

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 10Depth drilled 405 ft. Depth of completed well 320 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
soil zone, sandy	0	3	
sand, fine, brown	3	6	
packed clay & gravel, brown	6	58	
clay & gravel, brown	58	72	
gravel, med., brn.	72	75	50
clay & gravel, brn.	75	92	
cemented gravel	92	98	
clay & gravel, brn.	98	115	
clay & gravel, w/loose layers	115	130	
clay & gravel	130	178	
gravel, med., brn.	178	203	
clay & gravel, brn.	203	223	
gravel, med., brn.	223	250	
clay & gravel	250	265	
gravel, med.	265	270	
clay & gravel, brn.	270	405	

Work started 10/11 1976 Completed 11/1 1976Date well drilling machine moved off of well 11/3 1976

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Jerry Stooksberry Date 11/1, 1976
(Drilling Machine Operator)Drilling Machine Operator's License No. 801

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Jack Stooksberry, Jr.
(Person, firm or corporation) (Type or print)Address Rte. 2, Box 47, Lakeview, OR 97630[Signed] Jack Stooksberry Jr.
(Water Well Contractor)Contractor's License No. 211 Date 11/1, 1976

(USE ADDITIONAL SHEETS IF NECESSARY)