

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)
(Do not write above this line)

State Well No. 39/18-25cc

State Permit No. _____

(1) OWNER:

Name Mr Earl LaBranch
Address Lakeview, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
8 1/4" Diam. from 0 ft. to 48 ft. Gage 250
12" Diam. from 48 ft. to 181 ft. Gage 250
" Diam. from / ft. to / ft. Gage /

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Torch

Size of perforations 1/4 in. by 12 in.
128 perforations from 30 ft. to 165 ft.
perforations from / ft. to / ft.
perforations from / ft. to / ft.
perforations from / ft. to / ft.
perforations from / ft. to / ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Static level 49 ft. below land surface Date 11/17/55
Artesian pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Interstate Pump Co

Yield: 3000 gal./min. with UNKOWN ft. drawdown after 4 hrs.
" " " " " "

Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow _____ g.p.m. Date _____

Temperature of water _____ Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Cement
Depth of seal 60 ft.
Diameter of well bore to bottom of seal 16 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☐ Yes ☐ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(11) LOCATION OF WELL:

County Klamath Lake Driller's well number
SW 1/4 SW 1/4 Section 25 T. 39 R. 18 E W.M.

Bearing and distance from section or subdivision corner

947' North & 1086' East of the South west
Corner of Section 25

(12) WELL LOG:

Diameter of well below casing 10

Depth drilled 465 ft. Depth of completed well 465 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top Soil	0	4	
Gravel	45	5	
Clay brown with gravel	5	62	
Gravel Water	62	67	49
Brown clay with gravel	67	114	
Gravel	114	115	
Clay brown with some gravel	115	148	
Sand & gravel (water)	148	150	
Brown Clay	150	172	
Sand Gravel & clay	172	175	
White Clay	175	205	
Brown clay w/ gravel mixed	205	215	
White hard chalk	215	300	
Gravel	300	305	
White chalk	305	326	
Grey brown & black Lava	326	355	
Brown Clay	355	357	
Brown lava Porous	357	376	
Boulders & crevice	376	377	
Brown & grey Lava	377	399	
White Chalk	399	404	
Black & grey Lava	404	463	
Black Sand	463	465	

Work started 7/5 1955 Completed 11/17 1955
Date well drilling machine moved off of well 11/17 1955

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Walter L. Wilson Date Aug 25, 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. 201

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Wilson Drilling Contractor
(Person, firm or corporation) (Type or print)

Address P.O. Box 136, Merrill, Oregon

[Signed] Walter L. Wilson
(Water Well Contractor)

Contractor's License No. 169 Date Aug 25, 1969

(USE ADDITIONAL SHEETS IF NECESSARY)