

## NOTICE TO WATER WELL CONTRACTOR

The original and first copy  
of this report are to be  
filed with the

STATE ENGINEER, SALEM, OREGON  
within 30 days from the date  
of well completion.

# LAKE 2306

## WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No.

State Permit No.

OCT 28 1969

G 5101

## (1) OWNER:

Name Clyde FenimoreAddress Rt. 6 Box 564 Lakeview--Ore.  
Lakeview, ORE.

## (2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

## (3) TYPE OF WELL:

Rotary ☐ Driven ☐  
Cable ☒ Jetted ☐  
Auger ☐ Bored ☐

## (4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐  
Irrigation ☒ Test Well ☐ Other ☐

## (5) CASING INSTALLED:

Threaded ☐ Welded ☒  
16" Diam. from 0 ft. to 30 ft. Gage 1"  
" Diam. from ft. to ft. Gage  
" Diam. from ft. to ft. Gage

## (6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

| Size of perforations | in. by | in. |
|----------------------|--------|-----|
| perforations from    | ft. to | ft. |
| perforations from    | ft. to | ft. |
| perforations from    | ft. to | ft. |
| perforations from    | ft. to | ft. |
| perforations from    | ft. to | ft. |

## (7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

## (8) WATER LEVEL: Completed well.

Static level 41 ft. below land surface Date 9/16/69

Artesian pressure lbs. per square inch Date

## (9) WELL TESTS:

Drawdown is amount water level is  
lowered below static levelWas a pump test made? ☒ Yes ☐ No If yes, by whom? Pump Center

Id: 1800 gal./min. with 80 ft. drawdown after 7 hrs.

" 1250 " 41 " 7 "

" " " " "

Bailer test NO gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 62 Was a chemical analysis made? ☐ Yes ☒ No

## (10) CONSTRUCTION:

Well seal—Material used portland cement

Depth of seal 30 ft.

Diameter of well bore to bottom of seal 16 in.

Were any loose strata cemented off? ☐ Yes ☒ No DepthWas a drive shoe used? ☐ Yes ☒ NoDid any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

## (11) LOCATION OF WELL:

County Lake

Driller's well number

S. 1/4 Sec 31 T. 39S R. 19E W.M.

Bearing and distance from section or subdivision corner

## (12) WELL LOG:

Diameter of well below casing 16

Depth drilled 338 ft. Depth of completed well 338 ft.

Formation: Describe color, texture, grain size and structure of materials;  
and show thickness and nature of each stratum and aquifer penetrated,  
with at least one entry for each change of formation. Report each change  
in position of Static Water Level as drilling proceeds. Note drilling rates.

| MATERIAL             | From | To  | SWL |
|----------------------|------|-----|-----|
| top soil             | 0    | 2   |     |
| clay & sand          | 2    | 27  |     |
| yellow clay          | 27   | 33  |     |
| sand, gravel & clay  | 33   | 42  |     |
| yellow clay & sand   | 42   | 62  |     |
| sand & gravel        | 62   | 64  | 41  |
| yellow clay & sand   | 64   | 76  | 41  |
| fine gray sand       | 76   | 93  | 41  |
| gray clay & sand     | 93   | 133 | 41  |
| sand & gravel        | 133  | 136 | 41  |
| yellow clay & sand   | 136  | 158 | 41  |
| gray shale           | 158  | 170 | 41  |
| blue basalt          | 170  | 230 | 41  |
| creviced blue basalt | 230  | 251 | 41  |
| blue basalt          | 251  | 338 | 41  |

Work started 8/16/69 19 Completed 10/18/69 19

Date well drilling machine moved off of well 10/ 22 19 69

## Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Mate-  
rials used and information reported above are true to my best  
knowledge and belief.

[Signed] John A. Van Meter Date 10/22, 19 69  
(Drilling Machine Operator)

Drilling Machine Operator's License No. 118

## Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is  
true to the best of my knowledge and belief.

NAME John A. Van Meter  
(Person, firm or corporation) (Type or print)Address P.O. Box 204 Malin, Oregon[Signed] John A. Van Meter  
(Water Well Contractor)

Contractor's License No. 170 Date 10/22, 19 69

LAKE 2306

For Official Use Only:

Received Date:

County Well Log ID #

Well Identification Tag #

L 20469

**WELL IDENTIFICATION APPLICATION FORM****BUYER/CURRENT WELL OWNER:**Name: Richard Vaughn/Ken HinckleMailing Address: HC 60 BOX 2155City: Lakeview State: OR Zip: 97630 Phone: (541) 947-4558**WELL LOCATION:**County: Lake Owner's Well Number: 2306Township: 39 N or S, Range: 19 E or W; Section: 31 SW 1/4 NW 1/4Tax Lot Number: 100 Type of Well: water supply irrigation monitoring 1250 GPMStreet Address of Well (if different from above): NA**WELL INFORMATION: (do not complete remainder of application if well log is available)**Start Card Number: \_\_\_\_\_ Approx. Construction Date: 10/22/69Well Constructor: John A. VanMeterName of Owner at Time of Construction: Clyde FenimoreWell Depth (in feet): 338 Static Water Level (in feet): 41Diameter of Exposed Well Casing (in inches): 15"Does this well have a formal water right associated with it? Yes: X No: \_\_\_\_\_If Yes: Application #: G 5101 Permit #: G 4812 Certificate #: 40081

Please Return Completed Form to:

Lisa Joul  
Well Identification Program  
Oregon Water Resources Department  
158 12th Street NE  
Salem, OR 97310