

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 405/20E-10ca

State Permit No. _____

(1) OWNER:

Name DICK WAY (DOUBLE "D" LAND & CATTLE CO.)

Address HWY. 395 South
Lakeview, Oregon 97630

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
14" Diam. from 0 ft. to 416 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Factory-Cut

Size of perforations 1/8 in. by 3 in.
2,880 perforations from 36 ft. to 416 ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Contractor

Yield: 1,200 gal./min. with 80 ft. drawdown after 72 hrs.
1,700 " 95 " 72 "
" 2,500 " 130 " 72 "

Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow _____ g.p.m.

Temperature of water 58° Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement Grout

Well sealed from land surface to _____ 20 ft.

Diameter of well bore to bottom of seal 32 in.

Diameter of well bore below seal 24 in.

Number of sacks of cement used in well seal _____ 32 sacks

How was cement grout placed? Grout was pumped down a
2 inch pipe along the outside of the 24 inch
conductor casing to the bottom of the 32 inch
bore hole & slowly forced to the surface.

Was a drive shoe used? ☐ Yes ☒ No Plugs No Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 1/2 to 1/8

Gravel placed from 20 ft. to 416 ft.

(10) LOCATION OF WELL:

County Lake Driller's well number MR 519-77
N.E. 1/4 S.W. 1/4 Section 10 T. 40 S. 20 E. W.M.

Bearing and distance from section or subdivision corner

7 miles South of Lakeview Oregon on Hwy. 395
South; Then West 1.5 miles.

(11) WATER LEVEL: Completed well.

Depth at which water was first found 128 ft.

Static level 7 ft. below land surface. Date 8/6/77

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 9 7/8"

Depth drilled 616 ft. Depth of completed well 416 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil Zone	0	5	
Blue Clay	5	128	
Sand, Coarse, Blue	128	226	
(H2O Aquifer- 800 G.P.M.)			7
Clay & Sand stone Blue	226	272	
Sand, Coarse, Blue			
(H2O Aquifer-1500 G.P.M.)	272	385	
Clay & Sand Stone Layers	385	560	
Sand, Fine Blue			
(H2O Aquifer- (* or - 200)	560	590	
Clay & Sand Stone Layers	590	616	

RECEIVED

JUN 17 1979

WATER RESOURCES DEPT.
SALEM, OREGON

Work started 7/6/ 1977 Completed 8/5/ 1977

Date well drilling machine moved off of well 8/5/ 1977

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Gary Stooksberry Date 6/7/, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 801

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name RAPID WATER WELL DRILLING COMPANY
(Person, firm or corporation) (Type or print)

Address 545 North G Street, Lakeview, Oregon

[Signed] Gary Stooksberry
(Water Well Contractor)

Contractor's License No. 652 Date 6/7/, 1979