

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310-
within 30 days from the
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

Do not write above this line)

State Well No.

State Permit No.

RECEIVED
OCT 27 1969
STATE ENGINEER
SALEM, OREGON

G 5186

(1) OWNER:

Name Steve H. BaileyAddress Lakeview, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Aug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

12" Diam. from 0 ft. to 180 ft. Gage 250

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.Type of perforator used factory die cutSize of perforations 1/8 in. by 3 in.

6960 perforations from 50 ft. to 170 ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 32 ft. below land surface Date 10/25/69

Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static levelWas a pump test made? ☒ Yes ☐ No If yes, by whom? driller

Flow: 325 gal./min. with 82 ft. drawdown after 8 hrs.

" " " "

" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 51 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used cement w/ fill pipe to 18

Depth of seal 18 ft.

Diameter of well bore to bottom of seal 22 in.

Were any loose strata cemented off? ☐ Yes ☒ No DepthWas a drive shoe used? ☒ Yes ☐ NoDid any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/8 to 3/4

Gravel placed from 18 ft. to 170 ft.

(11) LOCATION OF WELL:

County Lake Driller's well number

NE 1/4 NW 1/4 Section 25 T. 40S R. 20E W.M.

Bearing and distance from section or subdivision corner

10 miles south of Lakeview, Oregon on
Hwy. 395

(12) WELL LOG:

Diameter of well below casing 12"

Depth drilled 200 ft. Depth of completed well 200 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
soil zone, gravelly &			
adobe	0	5	
gravel & clay w/boulders	5	42	
clay & gravel, brn.	42	47	
packed volcanic gravel	47	59	
gravel & boulders, loose	59	70	
gravel, med., brn.	70	103	
basalt boulders w/ hard			
clay, brown	103	122	
volcanic gravel, med.	122	145	
water zone			32
gravel & clay, brn.	145	200	

Work started 9/30 1969 Completed 10/25 1969

Date well drilling machine moved off of well 10/25 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Mate-
rials used and information reported above are true to my best
knowledge and belief.

[Signed] Jack Stooksberry Jr. Date 10/25, 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. 45

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

NAME Jack Stooksberry, Jr.
(Person, firm or corporation) (Type or print)

Address Rte. 2, Box 47, Lakeview, Ore.

[Signed] Jack Stooksberry Jr.
(Water Well Contractor)

Contractor's License No. 211 Date 10/25, 1969