

RECEIVED

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

FEB 23 1988

PLEASE TYPE or PRINT IN INK

Lake  
3009

26S/15E-286  
(for official use only)

WATER RESOURCES DEPT.

(1) OWNER: SALEM, OREGON  
Name Sam Pridale  
Address HC 61  
City SILVER LAKE State ORE

(2) TYPE OF WORK (check):  
New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐  
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL: (4) PROPOSED USE (check):  
Rotary Air ☐ Driven ☐ Domestic ☐ Industrial ☐ Municipal ☐  
Mud ☐ Dug ☐ Irrigation ☐ Thermal: ☒ Withdrawal ☐ Reinjection ☐  
Cable ☒ Bored ☐ Other: ☐ Piezometric ☐ Grounding ☐ Test ☐

(5) CASING INSTALLED: Steel ☒ Plastic ☐  
Threaded ☐ Welded ☒  
4" Diam. from 0 ft. to 80 ft. Gauge 1250  
" Diam. from ft. to ft. Gauge

LINER INSTALLED: Steel ☐ Plastic ☐  
Threaded ☐ Welded ☐  
NONE Diam. from ft. to ft. Gauge

(6) PERFORATIONS: Perforated? ☐ Yes ☒ No  
Size of perforations in. by in.  
perforations from ft. to ft.  
perforations from ft. to ft.  
perforations from ft. to ft.

(7) SCREENS: Well screen installed? ☐ Yes ☒ No  
Manufacturer's Name  
Type Model No.  
Diam. Slot Size Set from ft. to ft.  
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS: Drawdown is amount water level is lowered below static level  
Was a pump test made? ☐ Yes ☒ No If yes, by whom?  
Yield: gal./min. with ft. drawdown after hrs.  
Air test gal./min. with drill stem at ft. hrs.  
Per test 25 gal./min. with 0 ft. drawdown after 1 hrs.  
Artesian flow g.p.m.  
Temperature of water 50 Depth artesian flow encountered ft.

(9) CONSTRUCTION: Special standards: Yes ☐ No ☒  
Well seal—Material used portland Cement  
Well sealed from land surface to 80 ft.  
Diameter of well bore to bottom of seal 18 in.  
Diameter of well bore below seal 12 in.  
Amount of sealing material 54 sacks ☒ pounds ☐  
How was cement grout placed? pumped  
Was pump installed? no Type HP Depth ft.  
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.  
Did any strata contain unusable water? ☐ Yes ☒ No  
Type of Water? depth of strata  
Method of sealing strata off  
Was well gravel packed? ☐ Yes ☒ No Size of gravel:  
Gravel placed from ft. to ft.

(10) LOCATION OF WELL by legal description:  
County Lake 1/4 NW of Section 28 of  
Township 26 South Range 15 East WM.  
Tax Lot 26751 Lot Block Subdivision  
MAILING ADDRESS OF WELL (or nearest address) HC 61  
SILVER LAKE, ORE

(11) WATER LEVEL OF COMPLETED WELL:  
Depth at which water was first found 122 ft.  
Static level 26' ft. below land surface. Date 1-20-88  
Artesian pressure lbs. per square inch. Date

(12) WELL LOG: Diameter of well below casing 12"  
Depth drilled 412 ft. Depth of completed well 412 ft.  
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

| MATERIAL            | From | To  | SWL |
|---------------------|------|-----|-----|
| Top Soil Sandy Brn. | 0    | 2   |     |
| CLAY BRN.           | 2    | 122 |     |
| Rock Black Broken   | 122  | 145 | 26' |
| CLAY GRAY           | 145  | 168 |     |
| Rock Black Broken   | 168  | 259 | 26' |
| CLAY GRAY           | 259  | 325 |     |
| CLAY BRN.           | 320  | 350 |     |
| CLAY GRAY           | 350  | 412 |     |

Casing is one FT. Above ground  
12" hole from 80' to 192'  
8" hole from 192' to 412'

Date work started 1-3-88 /completed 2-21-88  
Date well drilling machine moved off of well 2-21 1988

(unbonded) Water Well Constructor Certification (if applicable):  
This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Claude Blackman Date 2-21, 1988

(bonded) Water Well Constructor Certification:  
Bond 9497438A Issued by Fidelity + Deposit Co. of Maryland  
(number) (Surety Company Name)  
On behalf of Claude Blackman  
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief:

(Signed) Claude Blackman  
(Water Well Constructor)

(Dated) 2-21-88

NOTICE TO WATER WELL CONSTRUCTOR  
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,  
SALEM, OREGON 97310  
within 30 days from the date of well completion.

SP\*46866-690