

RECEIVED

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

JUL 18 1988

(START CARD) #

1194

(1) OWNER:

Name Bureau of Land Management
Address P.O. Box 151
City Lakeview State Oregon Zip 97630

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☒ Other stock

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 405 ft.
Explosives used Yes ☐ No ☒ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
12"	0	20'	Bentonite	0	20'	12 sacks
10"	20'	405'				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other poured down

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	+1½	295½	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☒ Bailer ☐ Air ☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
25	0		1 hr.

Temperature of water 54* Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom no

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other no

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Lake Latitude _____ Longitude _____
Township 28S N or S, Range 13E E or W, WM.
Section 24 NW ¼ NW ¼
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) unknown

(10) STATIC WATER LEVEL:

200 ft. below land surface. Date 5-26-88
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 375'

From	To	Estimated Flow Rate	SWL
321	404	unknown	200'

(12) WELL LOG:

Ground elevation unknown

Material	From	To	SWL
Top Soil	0	10	
Orange Conglomerate	10	31	
Brown Conglomerate	31	55	
Mild Basalt	55	60	
Hard Grey Basalt	60	63	
Broken Basalt	63	272	
Lost Circulation @ 65'	272	287	
Broken Basalt	287	321	
Water-Bear. Sand & Gravels	321	404	
Hard Basalt	404	405	
Lost returns @ 65 ft. Water was apparently found at about 375' Static rose to 200 ft.			

Date started May 18, 1988 Completed June 10, 1988

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed [Signature] WWC Number 1276
Date June 23, 1988

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 608
Date 6-23-88