

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

State Well No. 38S/20E-22C

State Permit No. _____

(1) OWNER:

Name BURT CHAMBERSAddress LAKEVIEW, OREGON 97630

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

10" Diam. from 0 ft. to 20 ft. Gage .250
12" Diam. from 0 ft. to 14 ft. Gage .250
8" Diam. from 14 ft. to 172 ft. Gage .250

PERFORATIONS:

Perforated? ☒ Yes ☐ No.Type of perforator used Factory-Cut

Size of perforations 1/8 in. by 3 in.
480 perforations from 105 ft. to 165 ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Contractor

Yield: 750 gal./min. with 100 ft. drawdown after 8 hrs.
700 " 90 " 8 "
" 650 " 82 " 8 "

Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow 20 g.p.m. (Cased-Off)Temperature of water 80° Depth artesian flow encountered 128 ft.

(9) CONSTRUCTION:

Well seal—Material used Cement/Bentonite Grout

Well sealed from land surface to _____ 20 ft.

Diameter of well bore to bottom of seal 26 in.Diameter of well bore below seal 8 in.Number of sacks of cement used in well seal 36 sacksNumber of sacks of bentonite used in well seal 1 1/2 sacksBrand name of bentonite BAROID (Quik-Gel)

Number of pounds of bentonite per 100 gallons
of water 6 lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs No Size: location _____ ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

RECEIVED

MAY 4 1978

WATER RESOURCES DEPT.

(10) LOCATION OF WELL:

County LAKEDriller's well number AR 509-77

NW 1/4 SW 1/4 Section 22 T.38 S R. 20 E.W.M.

Bearing and distance from section or subdivision corner

1 mile due East of Hwy. # 140 Junction, Then
South on County Gravel Rd. for 1/2 mile.

(11) WATER LEVEL: Completed well.

Depth at which water was first found 128 ft.Static level 5 ft. below land surface. Date 4/14/78

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 8 InchDepth drilled 525 ft. Depth of completed well 525 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil Zone (Adobe-Loam)	0	3	
Clay & Boulders (Brown)	3	128	
Clay Stone Gravel (Fractured, Green) H2O Aquifer (150 G.P.M.)	128	132	5
Clay Stone (Solidified by Heat Hard Rock (White)	132	220	
Slate-Stone (Fractured, Red) H2O Zone (300 G.P.M.)	220	230	
Clay Stone (Solidified by Heat Hard Rock (White)	230	312	
Clay Stone Gravel (Fractured, Green) H2O Aquifer (100 G.P.M.)	312	316	
Clay Stone (Solidified by Heat Hard Rock (Green)	316	440	
Clay Stone Gravel (Fractured, Green) H2O Aquifer (200 G.P.M.)	440	445	
Clay Stone (Solidified by Heat White to Light Green	445	525	

Work started 5/20/ 19 77 Completed 4/14/ 1978Date well drilling machine moved off of well 4/15/ 1978

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Gary Stoksbury Date 4/15/ 1978
(Drilling Machine Operator)

Drilling Machine Operator's License No. 801

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name RAPID WATER WELL DRILLING COMPANY

(Person, firm or corporation)

(Type or print)

Address 545 North G Street, Lakeview, Oregon

[Signed] Gary Stoksbury
(Water Well Contractor)

Contractor's License No. 652 Date 4/15/ 1978