

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)
(Do not write above this line)

State Well No. 26/H-2

State Permit No. _____

(1) OWNER:

STATE ENGINEER

Name PAUL EVANS
Address RT. 4 Box 430 Roseburg, Oreg.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

8 Diam. from 00 ft. to 80 ft. Gage 4 in.
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations in. by in.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Static level 26 ft. below land surface Date 10/6/69

Artesian pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

" " " " " "

" " " " " "

Bailer test 10 gal./min. with 4 ft. drawdown after 2 hrs.

Artesian flow _____ g.p.m. Date _____

Temperature of water unknown Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Cement and mudDepth of seal 20 ft.Diameter of well bore to bottom of seal Approx. 12 in.Were any loose strata cemented off? ☐ Yes ☒ No Depth _____Was a drive shoe used? ☐ Yes ☒ NoDid any strata contain unusable water? ☒ Yes ☐ NoType of water? ALKALI depth of strata Approx. 35 ft.Method of sealing strata off CasingWas well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(11) LOCATION OF WELL:

County LAKE Driller's well number _____

Bearing and distance from section or subdivision corner

Approx. 400 ft. South from NW corner
of section 2 and 240 ft. East.

(12) WELL LOG:

Diameter of well below casing 8 in.Depth drilled 125 ft. Depth of completed well 92 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
top soil	0	to	4
HARD PAN	4	to	8
Small Gravel with Red cinders,	8	to	12
SAND, small gravel, small	12	to	36
Amount of yellow clay,			
BLACK SAND	36	to	75
WATER estimated 150			
g.p. hour.			
STATIC water level			
30 ft.			
yellow clay	75	to	80
Cinders and white pumice	80	to	92
Additional WATER			
Static water level	92		
increased 26 ft.			
Gray SAND	92		125
Caving - unable to			
get hole to hold up.			

Work started Sept. 15 1969 Completed Oct. 6 1969Date well drilling machine moved off of well Oct. 7 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Charles Jamphine Date Oct. 21, 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. _____

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME _____
(Person, firm or corporation) (Type or print)

Address _____

[Signed] _____
(Water Well Contractor)

Contractor's License No. _____ Date _____, 19____

(USE ADDITIONAL SHEETS IF NECESSARY)

Nov. 5, 1969

Dear Sir;

Indeed you will find water well
log. you will notice that I don't
own the land, I have rented this
place for over three years have
had to haul my drinking water
so got very tired of doing that
so I drilled a well for domestic
use although I probably wasn't
suppose to do it by law.

RECEIVED

NOV 7 1969

STATE ENGINEER
SALEM, OREGON

Sincerely yours,
Charles Tompkins
Front Rock, Oregon

97735