

JUN 29 1990

LAKE 4012 39S/19E/14bd  
(START CARD) # 4483

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

WATER RESOURCES DEPT.  
SALEM, OREGON

(1) OWNER: Well Number: 4483  
Name Loren & Kathryn Lucore  
Address HC 10 Box 463  
City Lakeview State OR Zip 97630

(2) TYPE OF WORK:  
 New Well  Deepen  Recondition  Abandon

(3) DRILL METHOD  
 Rotary Air  Rotary Mud  Cable  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval Yes No Depth of Completed Well 110 ft.  
Explosives used   Type Amount

HOLE SEAL Amount  
Diameter From To Material From To sacks or pounds  
16" 0 20 Cement 0 20 9 Sacks  
10" 20 110

How was seal placed: Method  A  B  C  D  E  
Backfill placed from ft. to ft. Material  
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:  
Diameter From To Gauge Steel Plastic Welded Threaded  
Casing: 10 3/4" 0 108 .25      
Liner:

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:  
 Perforations Method torch  
 Screens Type Material

From To Slot Number Diameter Tele/pipe Casing Liner  
60' 108' 1/8X6 390 size size

(8) WELL TESTS: Minimum testing time is 1 hour  
 Pump  Bailer  Air  Flowing Artesian  
Yield gal/min Drawdown Drill stem at Time  
120 21 Suction 35' 1 hr.  
120 21.9' 8 hrs.

Temperature of water 50° Depth Artesian Flow Found  
Was a water analysis done?  Yes By whom NO  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other  
Depth of strata: 28 to 52'

(9) LOCATION OF WELL by legal description:  
County Lake Latitude Longitude  
Township 39S N or S, Range 19E E or W, WM.  
Section 14 SE 1/4 NW 1/4  
Tax Lot 301 Lot Block Subdivision  
Street Address of Well (or nearest address) None

(10) STATIC WATER LEVEL:  
4 ft. below land surface. Date 6/1/90  
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:  
Depth at which water was first found 28'  
From To Estimated Flow Rate SWL  
28 52 30 4  
90 110 130 4

(12) WELL LOG: Ground elevation 4860  
Material From To SWL  
Top soil (loam) 0 4  
Brown clay 4 28  
Fine brown sand 28 52 4  
Sticky blue clay 52 90 4  
Black coarse sand w/medium gravel 90 110 4

Date started 8/1/89 Completed June 1, 1990

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
Signed \_\_\_\_\_ WWC Number \_\_\_\_\_  
Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.  
Signed *Loren & Kathryn Lucore* WWC Number 766  
Date 6/1/90