

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

LAKE
4030

JUL 25 1990

Permit # G 10817

(START CARD) # 22758

(1) OWNER:

Name Dan M Parker
Address HC 60 Box 1930
City Lakeview State OR Zip 97630

Well Number: 1

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☐ Rotary Air ☐ Rotary Mud ☒ Cable
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 340 ft.

Explosives used ☐ Yes ☒ No ☐ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
16	0	38	Cement	0	27	79 sacks
12	38	340				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	16	2.75	35	1/4"	☒	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
700	97 ft		2 hr.

Temperature of water 62° Depth Artesian Flow Found 100 ft

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County LAKE Latitude _____ Longitude _____
Township 39S N or S, Range 19E E or W, WM.
Section 21 NW 1/4 NW 1/4
Tax Lot 400 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) _____

(10) STATIC WATER LEVEL:

_____ ft. below land surface. Date _____
Artesian pressure 10 lb. per square inch. Date 7-13-90

(11) WATER BEARING ZONES:

Depth at which water was first found 20 ft

From	To	Estimated Flow Rate	SWL
20	22	10 GPM	10
various to bottom of hole			

(12) WELL LOG:

Ground elevation 4800 ft

Material	From	To	SWL
Top soil	0	6	
Blue Clay	6	20	
Sand	20	22	
Sand, Blue & yellow clay	22	192	
Sand	192	200	W/B
Sand - Blue clay	200	225	
Hard Blue clay	225	241	
Sand	241	245	W/B
sandy Blue clay	245	252	
Hard Blue clay	252	254	
Sand - Blue clay	254	280	
Sand - Blue & yellow clay	280	309	
Hard Blue clay	309	311	
White Sand & pea gravel	311	333	W/B
Sand - Blue & yellow clay	333	340	

Date started 7-5-89 Completed 7-23-90

(unbonded) Water Well Constructor Certification: Dan M Parker 60294391

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed Dan M Parker WWC Number 700225L
Date 7-23-90

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number _____
Signed _____ Date _____