

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

LAKE
24155

(START CARD) # W-26546

(1) OWNER: Well Number #2
Name Ed Stabb (Crump Ranch)
Address 145 Lakewood Rd.
City Walnut Creek State CA. Zip 94598

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☒ Other Stock Water

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 78 ft.
Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0	-25	Cement	0	-25	44 Sacks
6"	-25	-78				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	-65	.250	☒	☐	☐	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
Liner: 4 1/2"	-2	-78		☐	☐	☐	☐
				☐	☐	☐	☐

Final location of shoe(s) 65'

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Saw

☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
-58	-78	1/8	68	4 1/2"		☐	☒
		X 5				☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailor ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
15GPM		40'	1 hr.
48GPM		50'	1 hr.
80GPM		80'	2 hr.

Temperature of Water 88 Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Lake Latitude Longitude
Township 39S N or S. Range 24E E or W. WM.
Section 3 NW 1/4 SW 1/4
Tax Lot Lot 7527 Block Subdivision
Street Address of Well (or nearest address) West of County Rd
#3-10 Adel/Plush, Oregon

(10) STATIC WATER LEVEL:

30 ft. below land surface. Date 3/13/92
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 38'

From	To	Estimated Flow Rate	SWL
38'	83'	80 GPMS	30'

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
Topsoil	0	4	
Brown Sand	4	7	
Brown Sand & Gravel	7	12	
Gravel & Boulders	12	20	
Gravel	20	38	
Gravel - Water Bearing	38	51	30'
Brown Gravel & Rock	51	83	30'

Date started 3/11/92 Completed 3/13/92

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed Mike W. [Signature] WWC Number 1452
Date 3/20/92

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 693
Date 3/20/92