

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

LAKE 4369

LAKE WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED

MAR 9 - 1976

State Well No.

State Permit No. G-7129, G-9062

WATER RESOURCES DEPT.

SALEM, OREGON

(1) OWNER:

Name Warren J. Wegert (Ted Campbell)
Address 1726 NE 82nd Ave. Portland, Ore
97220

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

14" Diam. from + 1 ft. to 150 ft. Gage 250
" Diam. from " ft. to " ft. Gage "
" Diam. from " ft. to " ft. Gage "

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from " ft. to " ft.

Diam. Slot size Set from " ft. to " ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Blowing 1200 gal./min. with ft. drawdown after hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 50 Depth artesian flow encountered " ft.

(9) CONSTRUCTION:

Well seal—Material used cement

Well sealed from land surface to 22 ft.

Diameter of well bore to bottom of seal 18 in.

Diameter of well bore below seal 16 in.

Number of sacks of cement used in well seal 34 sacks

Number of sacks of bentonite used in well seal 0 sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons

of water lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from " ft. to " ft.

(10) LOCATION OF WELL:

County Lake Driller's well number

SE 1/4 NE 1/4 Section 29 T. 25S R. 11E W.M.

Bearing and distance from section or subdivision corner

1340' S & 1320' W of NE Corner Sec 29

(11) WATER LEVEL: Completed well.

Depth at which water was first found 58 ft.

Static level 44 ft. below land surface. Date 2/24/76

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12

Depth drilled 330 ft. Depth of completed well 330 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
sandy soil & congl	0	10	
caving gravel med	10	15	
brown clay	15	32	
green clay & brn sand	32	46	
brn sandstone fine	46	58	
gravel & gray sand (WB)	58	70	
blk sand & green clay	70	86	
soft gray rock	86	92	
brn sandstone med	92	115	
green clay congl	115	147	
coarse gravel & pumice(WB)	147	165	
blk sand w/tan & green clay	165	221	
blk sand/diatomaceous earth	221	247	
congl & coarse gravel	247	296	
diatomaceous earth	296	311	
congl	311	322	
brkn gray rock (WB)	322	328	
gray rock	328	330	44

Work started 2/17 1976 Completed 2/24 1976

Date well drilling machine moved off of well 2/24 1976

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] W. D. Williams Date 3/2, 1976.

(Drilling Machine Operator)

Drilling Machine Operator's License No. 864

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Crawford Well Drilling

(Person, firm or corporation)

(Type or print)

Address 3626 NW Coyner Redmond, Oregon

[Signed] John J. Johnson

(Water Well Contractor)

Contractor's License No. 595 Date 3/2, 1976.