

The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT

SALEM, OREGON 97310

within 30 days from the date

of well completion

RECEIVED
LAKE 4393

SEP 30 1977

STATE OF OREGON

(Please type or print)

WATER RESOURCES DEPT. Write above this line

SALEM, OREGON

PAGE 11

State Well No. 265/15E-24d

State Permit No. G-8134

(1) OWNER:

Name CODY J. PORTER FIELDAddress FT. ROCK, OR. 97735

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒14" Diam. from 1 1/2 ft. to 92 ft. Gage 1250

" Diam. from " ft. to " ft. Gage "

" Diam. from " ft. to " ft. Gage "

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.

perforations from " ft. to " ft.

perforations from " ft. to " ft.

perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from " ft. to " ft.

Diam. Slot size Set from " ft. to " ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Pump test 500 gal./min. with 80 ft. drawdown after 3 hrs.

Artesian flow g.p.m.

Temperature of water 52 Depth artesian flow encountered " ft.

(9) CONSTRUCTION:

Well seal—Material used PORTLAND CEMENT #1 & 2Well sealed from land surface to 92 ft.Diameter of well bore to bottom of seal 18 in.Diameter of well bore below seal 12 in.Number of sacks of cement used in well seal 15 sacksHow was cement grout placed? GRAVITY FLOWWas a drive shoe used? ☐ Yes ☒ No Plugs " Size: location " ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: "

Gravel placed from " ft. to " ft.

(10) LOCATION OF WELL:

County LAKE Driller's well numberCenter SE 1/4 Section 24 T. 26S R. 15E W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 90 ft.Static level 20 ft. below land surface. Date 9-23-77

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12Depth drilled 700 ft. Depth of completed well 700 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
BROWN SANDY SOIL FINE	0	2	
TAN CLAY CONG	2	31	
DK BRN CLAY & SAND	31	56	
BRN CLAY CONG.	56	90	
BLK ROCK BRN HD	90	95	
BROWN CLAY	95	120	
CS. BRN SANDSTONE	120	137	
BRN CLAY CONG. WB	137	179	28
BRN GRAY ROCK WB	179	193	
GRN CLAY & SAND	193	220	
BLK SAND FINE WB	220	268	W/S
BLK SAND & GRN CLAY	268	319	
BLK SAND & P. mic	319	357	
HD FRACTURED GRAY ROCK	357	384	
BLK SAND & P. mic WB	384	411	
BRN & GRN CLAY	411	444	
BLK SAND & P. mic WB	444	451	
GRN CLAY	451	459	
BLK SAND & P. mic	459	471	

Work started 9-12 19 77 Completed 9-23 19 77Date well drilling machine moved off of well 9-28 19 77

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] W. D. Williams Date 9-26, 19 77
(Drilling Machine Operator)

Drilling Machine Operator's License No. 864

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name William D. Williams
(Person, firm or corporation) (Type or print)

Address 3290 N.W. OAK LN. REDMOND, OR.

[Signed] William D. Williams
(Water Well Contractor)

Contractor's License No. 665 Date 9-26, 19 77

State Permit No. 6-8134

SALEM OREGON

SP*45656-119