

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

JUL 1 0 1975

SALEM, OREGON

State Well No. 279/17E-2
State Permit No. _____

(1) OWNER:

Name HENRY JENSEN
Address 835 KIMBALL SEASIDE CALIF 93955

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
12" Diam. from 0 ft. to 55 ft. Gage 375
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "

Bailer test 60 gal./min. with 1 ft. drawdown after 2 hrs.

Artesian flow g.p.m.

Temperature of water 55 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT & Puddled CLAY

Well sealed from land surface to 25 ft.

Diameter of well bore to bottom of seal 20 in.

Diameter of well bore below seal 12 in.

Number of sacks of cement used in well seal 4 sacks

Number of sacks of bentonite used in well seal sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County LAKE Driller's well number
SE 1/4 SE 1/4 Section 2 T. 27S R. 17E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 73 ft.
Static level 20.5 ft. below land surface. Date 6/25/75
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12

Depth drilled 288 ft. Depth of completed well 288 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
SOIL SANDY BROWN	0	2	
CLAY BROWN	2	38	
SAND FINE BROWN	38	40	
CLAY GRAY	40	46	
CLAY BLUE	46	73	
SAND BLACK FINE TO COARSE	73	74.5	
CLAY GRAY	74.5	164	
CLAY GREEN DARK	164	230	
PUMICE GRAVEL	230	233	
CLAY GREEN LIGHT COLOR	233	278	
PUMICE GRAVEL	278	279	
CLAY GRAY	279	284	
PUMICE GRAVEL	284	288	

Work started 6/10/ 1975 Completed 6/25/ 1975

Date well drilling machine moved off of well 6/27/ 1975

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Paul Blackman Date 7/8/ 1975
(Drilling Machine Operator)

Drilling Machine Operator's License No. 677

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name PAUL BLACKMAN DRILLING
(Person, firm or corporation) (Type or print)

Address P.O. Box 136 XMAS VALLEY ORE

[Signed] Paul Blackman
(Water Well Contractor)

Contractor's License No. 535 Date 7/8/ 1975