

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED
SEP 29 1972
STATE ENGINEER
SALEM, OREGON

STATE OF OREGON
(Please type or print)

State Well No. 26S/16E-8
State Permit No.

(1) OWNER:

Name James P. McCain
Address Route #1 Box 337 A
Beaver Creek, Oregon 97004

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☒ Other ☐

(5) CASING INSTALLED:

12" Diam. from 0 ft. to 25 ft. Gage .250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level Oregon ft. additional water

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Valley Pump.

Yield: 750 gal./min. with 32 ft. drawdown after 2 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 52 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 16 in.

Diameter of well bore below seal 12 in.

Number of sacks of cement used in well seal 9 sacks

Number of sacks of bentonite used in well seal sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons of water lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake Driller's well number
SW 1/4 1/4 Section 8 T26 R. 16 W.M.

Bearing and distance from section or subdivision corner
Approx. 1320 ft. South and 1320 ft.
East from the NW corner of the SW1/4

(11) WATER LEVEL: Completed well.

Depth at which water was first found 18 ft.

Static level 18 ft. below land surface. Date 7/2/72

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12

Depth drilled 205 ft. Depth of completed well 205 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	3	
Hard Pan	3	5	
Yellow Clay	5	18	
Some small gravel with water- estimate	18		18
5 gal. per hr.			
Blue Clay	18	60	
Yellow Clay	60	80	
Red Clay	80	100	
Small Pumice at 100			18
Oregon ft. additional water			
Klamath Falls, Estimate 200 gal. per hr.			18
Yellow Clay	100	112	
Black sand & Gravel	112	145	
Add. water			18
Yellow Clay	145	150	
Black Lava Rock	150	152	
Black Cinders-Add. Water	152	153	18
Yellow Clay	153	160	
Pumice-Add. Water	160	205	18
Work started 6/25/72 1972 Completed 9/10/72 1972			
Date well drilling machine moved off of well 9/10 1972			

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] James P. McCain Date Sep 25, 1972
(Drilling Machine Operator)

Drilling Machine Operator's License No.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name (Person, firm or corporation) (Type or print)

Address

[Signed] (Water Well Contractor)

Contractor's License No. Date 19