

Lake

51219

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

WELL I.D. # L 47629

START CARD # 133548

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Well Number

Name Pella Ranch Inc
Address PO Box 647
City BURNS State OR Zip 97720

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☐ No Depth of Completed Well 260 ft.Explosives used ☐ Yes ☐ No Type Amount

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
20"	0	37	Cement	0	37	20 Sack
14"	37	260	Ben	15	00	96 Sack

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E☐ Other 3/8 Hole Plug

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing 16"	0	37	250	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
1100		260	0.5

Temperature of water 55 Depth Artesian Flow FoundWas a water analysis done? ☐ Yes By whomDid any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Lake Latitude Longitude
Township 27 N or S Range 23 E or W. WM.
Section 4 S 1/4 SW 1/4
Tax Lot 200 Lot Block SubdivisionStreet Address of Well (or nearest address) 90 East 43 Mile
out Christmas Valley rd turn Butte Valley rd(10) STATIC WATER LEVEL: 90 4 mile81 ft. below land surface. Date 9-10-01

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found

From	To	Estimated Flow Rate	SWL
103	103	2 gal	
RECEIVED			
APR 07 2003			

(12) WELL LOG:

Ground Elevation

WATER RESOURCES DEPT.
SALEM, OREGON

Material	From	To	SWL
Hard Clay Brack	0	10	
Brown clay sand	10	23	
Green colored clay	23	84	
Pumice	84	103	43
Light Brown sandstone	103	140	
Cider pumice	140	155	43
Brown sand stone	155	230	
Sand, Cider Brown	230	255	
Light Clay Brack	255	260	43
RECEIVED			
FEB 03 2003			
OCT 17 2001			
WATER RESOURCES DEPT.			
SALEM, OREGON			

Date started 9-4-01 Completed 9-10-01

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 16541Signed [Signature] Date 10-13-01