

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537765)

LAKE 51627

WELL ID # L64070

(START CARD) # 166767

(1) OWNER 05 12
ROD HOGLAN
PO BOX 985
LAKEVIEW OR 97630

(2) TYPE OF WORK : NEW WELL

(3) DRILL METHOD : ROTARY MUD

(4) PROPOSED USE: Domestic

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Completed Well 119 ft.

Explosives used NO Type Amount

HOLE		SEAL		AMOUNT	
Diameter	From To	Material	From To	Sacks	
10"	0 120	BENTONITE	0 37	21	

How was seal Placed POURED DRY

Backfill placed from ft. to ft. Material

Gravel placed from 37 ft. to 120 ft. Size of Gravel #6

(6) CASING / LINER:

Dia.	From To	Gage	Material
CASING	5" +1 119	SDR 21	PLASTIC

Final location of shoe (s) CAP @ 119'

(7) PERFORATIONS / SCREENS:

METHOD	TYPE	MATERIAL
FACTORY	PVC	

From To	Slot size	Number	Dia.	Tele / pipe size
99 119	032	3680	5"	

(8) WELL TESTS:

Minimum testing time is 1 hour

TESTING METHOD	Yield GPM	Drawdown	Drill stem at	Time
AIR	60		60'	1 HOUR

Temperature of Water 58 F° Depth Artesian Flow Found

Was a water analysis done? NO By whom

Did any strata contain water not suitable for intended use? No

(9) LOCATION OF WELL by legal description :

County LAKE Latitude Longitude
Township 39 S Range 19 E
Section 13 NW 1/4 NE 1/4
Tax Lot 602 Lot Block Subdivision
Street Address of Well (or nearest address)
7398 HWY 140E LAKEVIEW

(10) STATIC WATER LEVEL:

17 ft. below land surface Date April 22, 2005
Artesian pressure Date

(11) WATER BEARING ZONES :

Depth at which water was first found	From To	Estimated Flow Rate	SWL
80	80 120	60 GPM	17

(12) WELL LOG:

	Ground Elevation	FROM	TO	SWL
SOIL	0	2		
BROWN CLAY & GRAVEL	2	4		
BROWN CLAY	4	10		
BROWN CLAY & BROWN SAND	10	20		
BROWN CLAY	20	25		
BLUE CLAY	25	39		
BROWN CLAY w/ BROWN & GREY	39			
SANDSTONE		80		
GREY CLAY & 1/8" GREY SAND	80	88	17	
BLUE CLAY & BLACK SAND	88	120	17	

RECEIVED

APR 28 2005

WATER RESOURCES DEPT
SALEM, OREGON

Date started April 22, 2005

Completed April 22, 2005

(Unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Mark West DATE 4-27-05 WWC # 1452

(Bonded) Water Well Constructor Certification: I accept responsibility for the construction alteration or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Chris Bonnell DATE 4-27-05 WWC # 693

