

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765 & OAR 690-205-0210)

WELL I.D. LABEL# L

START CARD #

ORIGINAL LOG #

(1) LAND OWNER

First Name Golden Rule Farms
Company Golden Rule Farms
Address PO Box 255
City Christmas Valley State OR Zip 97641

Owner Well I.D.

Last Name

(2) TYPE OF WORK

☒ Alteration (complete 2a & 10) ☐ Deepening ☐ Conversion
☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: ☐ Dia ☐ From ☐ To Gauge ☐ Stl ☐ Plstc ☐ Wld ☐ Thrld
Seal: ☐ Material ☐ From ☐ To Amt sacks/lbs

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☐ Industrial/ Commercial ☒ Domestic ☐ Irrigation ☐ Community
☐ Thermal ☐ Injection ☐ Livestock ☐ Dewatering
☐ Other

(5) BORE HOLE CONSTRUCTION

Depth of Completed Well 154 ft. Special Standard ☐ (Attach copy)BORE HOLE 174 ft. 174 ft. SEAL
Dia From To Material From To Amt sacks/lbs
12 0 154 Concrete 20 152 82 50
3/8 Barbute 0 20 35 50
Calculated 15How was seal placed: ☒ Other Barbute poured dry Method ☐ A ☐ B ☒ C ☐ D ☐ EBackfill placed from ft. to ft. Material Size Filter pack from ft. to ft. Material Size Explosives used: ☐ Yes Type Amount

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Pounds Actual Amount Pounds

(6) CASING/LINER

Casing/Liner ☒ Dia 6 + From 8 To 152 Gauge 250 Stl ☒ Plstc ☐ Wld ☒ Thrld
Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s)
Temp casing ☒ Yes Dia 12 From 1 To 15

(7) PERFORATIONS/SCREENS

Perforations Method Screens Type Material
Perf/S Casing/ Screen Dia From To Screen/Slot width Slot length # of slots Tele/ pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailor ☒ Air ☐ Flowing Artesian
Yield gal/min 100 Drawdown Drill stem/Pump depth 150 Duration (hr) 1Temperature 54 °F Lab analysis ☐ Yes By
Water quality concerns? ☐ Yes (describe below) TDS amount 7800 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County Lake Twp 27S N/S Range 17E E/W WMSec 16 SE 1/4 of the SE 1/4 Tax Lot 1400

Tax Map Number

Lot

Lat " or 43.223451 DMS or DDLong " or -120.701142 DMS or DDC Street address of well ☒ Nearest address ChristmasNW Corner Golden Ln & S. Rainbow Rd Valley

(10) STATIC WATER LEVEL

Existing Well / Pre-Alteration Date 5/15/2023 SWL(psi) + SWL(ft) 32
Completed Well
Flowing Artesian? ☐ Dry Hole? ☐ 37.81

WATER BEARING ZONES

SWL Date From To Depth water was first found 70
Est Flow SWL(psi) + SWL(ft)
4/10/23 70 90 20 32
4/18/23 110 120 100 92

(11) WELL LOG

Ground Elevation 4320
Material From To
Top Soil 0 6
Grey Clay 6 12
Green Clay 12 70
Pumice (clay + silt) (W.B.) 70 90
Brown Clay 90 110
Pumice Clay (W.B.) 110 120
Solid Green Clay 120 154
Green Clay / Pumice (W.B.) 154 174

RECEIVED

MAY 15 2023

OWRD

Date Started 4/18/2023 Completed 5/15/2023(unbonded) Water Well Constructor Certification - OWRD Rep.

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date 5/15/2023Signed (bonded) Water Well Constructor Certification - Landowner

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number Date 5-15-23Signed Contact Info (optional) Ezekiel Hart 5-15-23

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version: 0.95