

STATE OF OREGON
WATER SUPPLY WELL REPORT

LAKE 55208

WELL I.D. LABEL# L

Page 1 of 3

158193

START CARD #

1082050

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

6/9/2026

(1) LAND OWNER

Owner Well I.D.

First Name Last Name

Company SUSTAINABLE NORTHWEST

Address 233 SW NAITO PKWY, #200

City PORTLAND State OR Zip 97204

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal:

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☐ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☒ Livestock ☐ Dewatering

☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 342.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	38	Bentonite Chips	0	38	25	S
6	38	342			Calculated	17.75	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POUR DRY&HYDRATED

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 5/26/2026 Begin Time 16 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒	2	38	0.250	ST	☒		OUT.	38
L	4		22	342	Sch40	PL		☒		

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method FACTORY

Screens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Perf	Liner	4	322	342	.032	3	960	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Pump	11	0	300	1

Temperature 67 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 147 ppm

From	To	Description	Amount	Units
------	----	-------------	--------	-------

(9) LOCATION OF WELL (legal description)

County LAKE Twp 37.00 S N/S Range 16.00 E E/W WM

Sec 30 NE 1/4 of the SW 1/4 Tax Lot 1300

Tax Map Number Lot

Lat ° ' " or 42.33033000 DMS or DD

Long ° ' " or -120.87550000 DMS or DD

☐ Street address of well ☒ Nearest address

HIGHWAY 140E BLY,OR

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	6/1/2026			226
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 241.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
5/29/2026	241	342	20			226

(11) WELL LOG

Ground Elevation 4938.10 FT

Material	From	To
TOP SOIL	0	9
GREY BASALT	9	241
GREY BASALT W/ RED CINDER (WB)	241	342

Construction

Begin Date 5/26/2026 Begin Time 12 05 End Date 6/1/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2106 Date 6/9/2026

Signed RILEY AMBERS (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1844 Date 6/9/2026

Signed COLTER CHANCELLOR (E-filed)

Drilling Company: Chancellor Drilling & Pump

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

6/9/2026

[illegible][illegible][illegible]

Assistant Name	Type	#
BRAYDEN ROACH	HELPER WATER	8888998

[illegible]

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

LAKE 55208

6/9/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 42.33033000 Datum: WGS84

Longitude: -120.87550000

Township/Range/Section/Quarter-Quarter Section:

WM37.00S16.00E30NESW

Address of Well:

HIGHWAY 140E BLY,OR

Well Label: 158193

Printed: June 9, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

