

STATE OF OREGON
WATER SUPPLY WELL REPORT

LAKE 55222

WELL I.D. LABEL# L

Page 1 of 3

159357

START CARD #

1082805

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/12/2026

(1) LAND OWNER

Owner Well I.D.

First Name MARVIN

Last Name CURRIE

Company

Address PO BOX 778

City OAKRIDGE

State OR

Zip 97463

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 240.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
11	0	39	Bentonite	0	39	36	S
6	39	240			Calculated	28	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: BENTONITE

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 7/15/2026 Begin Time 10 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Actual Amount

(6) CASING/LINER

C/L	Dia	+ From To Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒ 1 39 0.250	ST	☒			
L	4.5	☐ 4 240 1220	PL		☒		

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method saw

Screens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size
		4.5	220	240	.25	3	250	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	50		240	1
Air	30		240	1

Temperature 52 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 299 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County LAKE Twp 27.00 S N/S Range 17.00 E E/W WM

Sec 33 NE 1/4 of the SE 1/4 Tax Lot 1702

Tax Map Number Lot

Lat ° ' " or 43.18432000 DMS or DD

Long ° ' " or -120.70319000 DMS or DD

☐ Street address of well ☒ Nearest address

PETS LAKE LN UP 1 MILE CHRISTMAS VALLEY OR 97641

(10) STATIC WATER LEVEL

	Date	SWL(psi)	+	SWL(ft)
Existing Well / Pre-Alteration				
Completed Well	7/17/2026			169
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 220.00

SWL Date From To Est Flow SWL(psi) + SWL(ft)

7/16/2026	220	240	30		169

(11) WELL LOG

Ground Elevation 4443.02 FT

Material	From	To
top soil	0	1
Boulders	1	5
gray lava rock	5	90
black lava rock	90	112
brown lava rock	112	126
red lava rock	126	139
gray lava rock	139	142
black lava rock	142	168
red lava rock	168	193
gray lava rock	193	216
Broken lever rock	216	226
red ciders	226	240

Construction

Begin Date 7/14/2026 Begin Time 08 00 End Date 7/17/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1654 Date 8/12/2026

Signed TOM SEARCH (E-filed)

Drilling Company: Tom Search

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

pettus lake ln 1 mile up on right Christmas Valley or 97641

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

LAKE 55222

8/12/2026

Map of Hole

