

STATE OF OREGON
WATER SUPPLY WELL REPORT

LAKE 55233

WELL I.D. LABEL# L

Page 1 of 3

START CARD #

ORIGINAL LOG #

159358

1083042

9/9/2026

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

(1) LAND OWNER

Owner Well I.D.

First Name GARRICK

Last Name LAWSON

Company

Address 223 E D ST

City CULVER

State OR

Zip 97734

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal:

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☒ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 240.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
11	0	38	Bentonite	0	38	35	S
6	38	160			Calculated	30	
5	160	240			Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: BENTONITE

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 8/3/2026 Begin Time 11 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Actual Amount

(6) CASING/LINER

C/L	Dia	+ From To Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒ 2 38 0.250	ST	☒			
L	5	☐ 4 160 0.188	ST	☒			

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	20		240	1

Temperature 55 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 299 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County LAKE Twp 32.00 S N/S Range 13.00 E E/W WM

Sec 36 SE 1/4 of the NW 1/4 Tax Lot 1102

Tax Map Number Lot

Lat ° ' " or 42.75612283 DMS or DD

Long ° ' " or -121.12894660 DMS or DD

☐ Street address of well ☒ Nearest address

32S 13E 36 1102 3207RD TO RAIL ROAD TRACKS TURN LEFT 1 MILE IN

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	8/12/2026			85
Flowing Artesian?	☐	Dry Hole?	☐	

WATER BEARING ZONES

Depth water was first found 180.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
8/11/2026	180	185	20			85

(11) WELL LOG

Ground Elevation 5005.95 FT

Material	From	To
top soil	0	2
Boulders and clay	2	5
brown lava rock	5	19
brown lava rock	5	19
red lava rock	19	26
red lava rock	19	26
black lava rock	26	50
red lava rock	50	75
brown lava rock	75	96
Broken lower rock red	96	125
Fractured gray lava rock	125	136
Fractured gray lava rock	125	136
Fractured red lava rock	136	149
Black fractured lava rock	149	169
Gray Lava Brock with fractures	169	205
Blue clay stone	205	240

Construction

Begin Date 8/3/2026 Begin Time 10 00 End Date 8/12/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1654 Date 9/9/2026

Signed TOM SEARCH (E-filed)

Drilling Company: Tom Search

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

(2a) PRE-ALTERATION

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd

Material	From	To	Amt	sacks/lbs

(5) BORE HOLE CONSTRUCTION

BORE HOLE			SEAL			sacks/ lbs	
Dia	From	To	Material	From	To		Amt
			Calculated				
			Calculated				
			Calculated				
			Calculated				

FILTER PACK			
From	To	Material	Size

(6) CASING/LINER

[illegible]

(7) PERFORATIONS/SCREENS

[illegible]

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)

Water Quality Concerns

[illegible]

(10) STATIC WATER LEVEL

[illegible]

(11) WELL LOG

[illegible]

Name of person(s) who assisted with construction and Trainee License # / Helper #

Assistant Name	Type	#
JODY SULLEN	HELPER WATER	8888996

Comments/Remarks

--

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

LAKE 55233

9/9/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department
725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 42.75612283 Datum: WGS84

Longitude: -121.12894660

Township/Range/Section/Quarter-Quarter Section:
WM32.00S13.00E36SENW

Address of Well:

32S 13E 36 1102 3207RD TO RAIL ROAD TRACKS TURN LEFT 1 MILE IN

Well Label: 159358

Printed: September 9, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

