

STATE OF OREGON
WATER SUPPLY WELL REPORT

LAKE 55235

WELL I.D. LABEL# L

145380

START CARD #

1055409

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

9/14/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name THERESALast Name CLIFFCompany BELL "A" LAND & CATTLE COMPANY, INC.Address PO BOX 97City LAPINEState ORZip 97739**(2) TYPE OF WORK**☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd

Material From To Amt sacks/lbs

Seal:

(3) DRILL METHOD☒ Rotary Air ☒ Rotary Mud ☐ Cable ☐ Auger☒ Reverse Rotary ☐ Other _____**(4) PROPOSED USE**☐ Domestic ☒ Irrigation ☐ Community☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other _____**(5) BORE HOLE CONSTRUCTION**Special Standard ☐ (Attach copy)Depth of Completed Well 502.00 ft.

BORE HOLE			SEAL				sacks/
Dia	From	To	Material	From	To	Amt	lbs
20	0	176	Bentonite Chips	0	27	65	S
16	176	373	Calculated				27.26
9.88	373	502	Cement	27	176	264	S
				Calculated			
							88.47

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☒ Other: POURED DRY

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____Seal Placement Begin Date 1/24/2022 Begin Time 11 00**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount _____

Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	16	☒	1	176	0.375	ST	☒			
L	12		156	373	0.250	ST	☒			

Temp casing ☐ Yes Dia _____ From + ☐ _____ To _____**(7) PERFORATIONS/SCREENS**Perforations Method Factory Saw

Screens Type _____ Material _____

Perf/	Casing/	Screen	Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/
Perf	Casing		12	186	252	.095	3	1580	Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Pump	2350	3	150	12

Temperature 54 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 245 mg/L

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County LAKE Twp 28.00 S N/S Range 14.00 E E/W WMSec 15 SE 1/4 of the SW 1/4 Tax Lot 100

Tax Map Number _____ Lot _____

Lat _____ ° _____ ' _____ " or 43.13502290 DMS or DD

Long _____ ° _____ ' _____ " or -121.05019927 DMS or DD

☒ Street address of well ☐ Nearest addressOFF HIGHWAY 31, SILVER LAKE, OR 97638**(10) STATIC WATER LEVEL**

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	1/28/2022			31
Flowing Artesian?		☐	Dry Hole?	
		☐		

WATER BEARING ZONES

Depth water was first found 17.00

SWL Date From To Est Flow SWL (psi) + SWL (ft)

1/18/2022	17	65	40		17
1/19/2022	80	150	100		31
1/22/2022	176	502	3000		31

(11) WELL LOGGround Elevation 4343.75 FT

Material	From	To
Grayish Clay	0	4
Gray Sand, Gravel & Boulders	4	30
Sand, Gravel & Brown Clay	30	50
Sand & Gravel Mix with Gray Clay	50	80
Gray Clay & Boulders	80	100
Sand Black	100	130
Brown, Gray Clay with Black Sand Seams	130	150
Brown & Gray Clay	150	165
Black & Red Rock	165	223
Gray Rock & Red Cinders	223	250
Brown & Black Sand with Claystone	250	370
Reddish Orange Rock & Reddish Brown Sandstone	370	480
Gray Boulders	480	502

Construction

Begin Date 1/17/2022 Begin Time 08 30 End Date 1/28/2022**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1385 Date 9/10/2026Signed ROBERT BUCKNER (E-filed)Drilling Company: Western Water Development, Corp.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

Ran 16" & 12" casing string together with a 16" x 12" bell reducer at 176'. also installed a double shale trap at that point to install Cement and Bentonite seal from that point back to surface.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

LAKE 55235

9/14/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 43.13502290 Datum: WGS84

Longitude: -121.05019927

Township/Range/Section/Quarter-Quarter Section:

WM28.00S14.00E15SESW

Address of Well:

OFF HIGHWAY 31, SILVER LAKE, OR 97638

Well Label: 145380

Printed: July 1, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor



100

145380

1700

100

