

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 205/17E-35

State Permit No. _____

(1) OWNER:

Name Lynn Fus
Address P.O. Box 335 Christmas Vly. OR. 97635

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
☐ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

6" Diam. from +1 ft. to 79 ft. Gage Plastic
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used _____

Size of perforations _____ in. by _____ in.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.
" _____ " _____ " _____ "
" _____ " _____ " _____ "
Pump test 30 gal./min. with _____ ft. drawdown after _____ hrs.
Artesian flow _____ g.p.m.
Temperature of water _____ Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 79 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 20 sacks
How was cement grout placed? Cement was mixed up. 1" pipe run down along side & pressure grouted in.
Was a drive shoe used? ☐ Yes ☒ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Lake Driller's well number _____
1/4 1/4 Section 35 T. 26S R. 17E W.M.

Bearing and distance from section or subdivision corner

NW 1/4 SE 1/4 NE 1/4 SE 1/4

(11) WATER LEVEL: Completed well.

Depth at which water was first found 60 ft.
Static level 21 ft. below land surface. Date 7/3/80
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 390 ft. Depth of completed well 390 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown Clay	0	14	
Black Clay	14	16	
Brown Clay	16	36	
Blue Stone	36	46	
Brown Stone w/B	46	65	
Grey Stone	65	140	
Brown Stone	140	360	
Pumice w/B	360	365	
Grey Stone	365	390	

RECEIVED

AUG 18 1980

WATER RESOURCES DEPT
SALEM, OREGON

Work started 7/1 1980 Completed 7/3 1980
Date well drilling machine moved off of well 7/3 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Mel Search Date 7/10 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 699

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Mel Search Well Drilling
(Person, firm or corporation) (Type or print)

Address P.O. Box 432 Lebanon, OR.

[Signed] Mel Search
(Water Well Contractor)

Contractor's License No. 567 Date 7/10 1980