

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

WATER RESOURCES DEPT
SALEM, OREGON

RECEIVED
1/30/81
NOV 14 1979
State Well No. 26518E-5ad
State Permit No.

(1) OWNER:

Name C. Wade Brown
Address 6169 Pettigrew - Bend, Ore 97725

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☐
14" Diam. from 0 ft. to 19 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations	in.	by	in.
perforations from		ft. to	ft.
perforations from		ft. to	ft.
perforations from		ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Flow	gal./min. with	ft. drawdown after	hrs.
"	"	"	"
"	"	"	"
Bailer test 900	gal./min. with	ft. drawdown after 3	hrs.
Artesian flow	g.p.m.		
Temperature of water	Depth artesian flow encountered		ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 16 1/2 in.
Diameter of well bore below seal 14 in.
Number of sacks of cement used in well seal 8 sacks
How was cement grout placed? pressure grouted

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake Driller's well number 67
SE 1/4 NE 1/4 Section 5 T. 26S R. 17E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 250 ft.
Static level 114 ft. below land surface. Date 17 Sept 79
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 14

Depth drilled 356 ft. Depth of completed well 350 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown Gray basalt	0	4	
Brown red basalt	4	6	
Gray brown basalt	6	16	
Gray basalt	16	40	
Broken brown rock	40	46	
Broken brown rock	46	69	
Brown sandstone, med	69	85	
Diatomaceous earth	85	109	
Blue Clay	109	130	
Dark Green Clay	130	250	
Black sand water bearing	250	289	
Rock - med	289	291	
Broken porous lava	291		

RECEIVED

Work started Sept 13 1979 Completed Sept 19 1979
Date well drilling machine moved on well Sept 19 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Alan Adams Date Sept 18, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1302

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Tyler Adams (Person, firm or corporation) (Type or print)

Address Tyler Adams Rt 3 Box 122X

[Signed] Tyler Adams (Water Well Contractor) Hillsboro Ore 97123

Contractor's License No. 690 Date Sept 18, 1979