

**NOTICE TO WATER WELL CONTRACTOR**

The original and first copy of this report are to be filed with the

**RECEIVED WATER WELL REPORT**  
**STATE OF OREGON**

*Lake 681*

STATE ENGINEER, SALEM, OREGON 97310  
 within 30 days from the date of well completion.

JUL 20 1977

(Please type or print)

(Do not write above this line)

State Well No. 26S/18E-30  
 State Permit No. G-8245?

WATER RESOURCES DEPT.

**(1) OWNER:**

Name KENYON MOREHOUSE  
 Address Box 123 CHRISTMAS VALLEY ORE

**(2) TYPE OF WORK (check):**

New Well  Deepening  Reconditioning  Abandon   
 If abandonment, describe material and procedure in Item 12.

**(3) TYPE OF WELL:**

Rotary  Driven   
 Cable  Jetted   
 Dug  Bored

**(4) PROPOSED USE (check):**

Domestic  Industrial  Municipal   
 Irrigation  Test Well  Other

**CASING INSTALLED:**

10" Diam. from 0 ft. to 40 ft. Gage 350  
 " Diam. from ..... ft. to ..... ft. Gage .....  
 " Diam. from ..... ft. to ..... ft. Gage .....

**PERFORATIONS:**

Perforated?  Yes  No.

Type of perforator used

Size of perforations in. by in.  
 ..... perforations from ..... ft. to ..... ft.  
 ..... perforations from ..... ft. to ..... ft.  
 ..... perforations from ..... ft. to ..... ft.

**(7) SCREENS:**

Well screen installed?  Yes  No

Manufacturer's Name ..... Model No. ....  
 Type ..... Slot size ..... Set from ..... ft. to ..... ft.  
 Diam. .... Slot size ..... Set from ..... ft. to ..... ft.

**(8) WELL TESTS:**

Drawdown is amount water level is lowered below static level

Was a pump test made?  Yes  No If yes, by whom?

Yield: 100 gal./min. with 4 ft. drawdown after 1 hrs.  
 " " " " " " " "

Bailer test 600 gal./min. with 3 ft. drawdown after 3 hrs.

Artesian flow g.p.m.

Temperature of water ..... Depth artesian flow encountered ..... ft.

**(9) CONSTRUCTION:**

Well seal—Material used CEMENT  
 Well sealed from land surface to 40 ft.  
 Diameter of well bore to bottom of seal 13 in.  
 Diameter of well bore below seal 9 in.  
 Number of sacks of cement used in well seal 10 sacks  
 Number of sacks of bentonite used in well seal ..... sacks  
 Brand name of bentonite .....  
 Number of pounds of bentonite per 100 gallons of water ..... lbs./100 gals.  
 Was a drive shoe used?  Yes  No Plugs ..... Size, location ..... ft.  
 Did any strata contain unusable water?  Yes  No  
 Type of water? ..... depth of strata .....  
 Method of sealing strata off .....  
 Was well gravel packed?  Yes  No Size of gravel: .....  
 Gravel placed from ..... ft. to ..... ft.

**(10) LOCATION OF WELL:**

County LAKE Driller's well number .....  
 1/4 1/4 Section 30 T. 26 R. 18 E W.M.  
 Bearing and distance from section or subdivision corner

**(11) WATER LEVEL: Completed well.**

Depth at which water was first found ..... ft.  
 Static level 16 ft. below land surface. Date Jun 30/77  
 Artesian pressure ..... lbs. per square inch. Date

**(12) WELL LOG:**

Diameter of well below casing 9 ft.  
 Depth drilled 110 ft. Depth of completed well 110 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
FINE SAND BROWN	0	4	
BROWN CLAY	4	25	
GREEN CLAY	25	35	
BLACK CLAY	35	60	
BLACK CLAY & SAND	60	80	
BLACK SAND	80	110	

Work started Jun 30 1977 Completed Jun 30 1977

Date well drilling machine moved off of well JUNE 30 1977

**Drilling Machine Operator's Certification:**

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Melvin Search Date July 12, 1977  
 (Drilling Machine Operator)

Drilling Machine Operator's License No. G-99

**Water Well Contractor's Certification:**

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name MELVIN SEARCH WELL DRILLING  
 (Person, firm or corporation) (Type or print)

Address P.O. Box 123 LAKE ANTHONY ORE

[Signed] Melvin Search  
 (Water Well Contractor)

Contractor's License No. 567 Date July 12, 1977