

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No.

265/18E-31bb

State Permit No.

(1) OWNER:

Name MORSE
MORRIS
Address PO Box 240
Christmas Valley Oregon 97638

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

" Diam. from 0 ft. to 180 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "
" " " "
Bailer test 1200 gal./min. with ft. drawdown after 1 hrs.
Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used cement
Well sealed from land surface to 100 ft.
Diameter of well bore to bottom of seal 16 1/2 in.
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal 55 sacks
How was cement grout placed? pressure grouted

Was a drive shoe used? ☐ Yes ☒ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____
Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Lake Driller's well number 93
NW 1/4 NW 1/4 Section 31 T.26S R.18E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 251 ft.
Static level 23 ft. below land surface. Date Apr. 23 - 80
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 10"

Depth drilled 361 ft. Depth of completed well 360 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown sandy top soil	0	2	
Brown sandy clay	2	25	
Green clay	25	250	
white pumice w/b	250	251	
Green clay	251	306	
white pumice w/b	306	311	
Green clay	311	334	
white pumice w/b	334	340	
Green clay	340	355	
white pumice w/b	355	358	
Green clay	358	361	23
DECEASED			
DECEASED			
WATER RESOURCES DEPT			
SALEM, OREGON			

Work started Apr. 23 1980 Completed April 23 1980

Date well drilling machine moved off of well April 24 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Stan L Adams Date April 23 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1302

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Lyle Adams
(Person, firm or corporation) (Type or print)

Address PO Box 1228 Hillsboro Or, 97123

[Signed] Lyle Adams
(Water Well Contractor)

Contractor's License No. 690 Date Apr. 24 1980