

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON JUL 2 1975

State Well No. 265/19E-5

(Please type or print)

WATER RESOURCES DEPT.

Permit No.

SALEM, OREGON

(1) OWNER:

Name Lyle Damewood

Address Fort Rock, Oregon 97735

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
12" Diam. from + 1 ft. to 42 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 40 gal./min. with 0 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water 50 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used cement

Well sealed from land surface to 25 ft.

Diameter of well bore to bottom of seal 16 in.

Diameter of well bore below seal 12" to 130' - 8" to 150'

Number of sacks of cement used in well seal 18 sacks

Number of sacks of bentonite used in well seal 0 sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons

of water lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake Driller's well number

NW 1/4 SE 1/4 Section 5 T. 26S R. 19E W.M.

Bearing and distance from section or subdivision corner

2112' N & 1584' W of SE corner Sec 5

(11) WATER LEVEL: Completed well.

Depth at which water was first found 20 ft.

Static level 14 ft. below land surface. Date 6/18/75

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12 & 8

Depth drilled 150 ft. Depth of completed well 150 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
brown sandy soil	0	2	
brown clay	2	5	
brown sand w/ some clay	5	15	
brn clay congl (WB)	15	25	
green claystone	25	53	
brn & tan clay congl (WB)	53	72	
gray clay congl	72	92	
tan clay congl (WB)	92	112	
tan clay congl	112	121	
brk hd gray rock congl	121	130	
brk hd gray rock congl	130	135	
hd gray rock (WB)	135	150	14

Work started 6/ 12 19 75 Completed 6/18 1975

Date well drilling machine moved off of well 6/18 1975

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] W. A. Williams Date 6/27, 1975
(Drilling Machine Operator)

Drilling Machine Operator's License No. 864

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Crawford Well Drilling
(Person, firm or corporation) (Type or print)

Address 3626 N.W. Coyner Redmond, Ore.

[Signed] John J. Jheron
(Water Well Contractor)

Contractor's License No. 595 Date 6/27, 1975