

The original and first copy of this report are to be filed with the

RECEIVED

WATER WELL REPORT

WATER RESOURCES DEPARTMENT

SALEM, OREGON 97310

within 30 days from the date of well completion.

MAR 16 1979

STATE OF OREGON

(Please type or print)

WATER RESOURCES DEPT.

(Do not write above this line)

State Well No.

265/19E-7cd

State Permit No.

G-8271 Well #1

(1) OWNER:

SALEM, OREGON

Name Anthony J. Stewart
Address P.O. Box 136 97138
Christmas Valley, Ore

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒1 1/4" Diam. from 0 ft. to 88 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ NoManufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?Yield: gal./min. with ft. drawdown after hrs.
" " " "
" " " "

Bailer Test 1400 gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement Grout
Well sealed from land surface to 88 ft.
Diameter of well bore to bottom of seal 16 1/2 in.
Diameter of well bore below seal 12 in.
Number of sacks of cement used in well seal 99 1/2 sacks
How was cement grout placed? pressure groutedWas a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.Did any strata contain unusable water? ☒ Yes ☐ NoType of water? sandy depth of strata 68-78"Method of sealing strata off cased & pressure groutWas well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake Driller's well number 38

SE 1/4 SW 1/4 Section 7 T. 26S R. 19E W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 68 ft.Static level 14 ft. below land surface. Date Mar 12

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12"Depth drilled 100 ft. Depth of completed well 99 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Sandy soil	0	6	
brassy clay	6	20	
gray & brassy clay	20	68	
fine black sand	68	78	
gray basalt - hard	78	93	
lava broken porous	93	100	
black 1400 gal			
more solid rock	100	-	

Work started march 11 1979 Completed march 14 1979Date well drilling machine moved off of well march 15 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Stan J. Adams Date march 14 1979
(Drilling Machine Operator)Drilling Machine Operator's License No. 1302

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Lyle R. Adams (Type or print)
(Person, firm or corporation)Address P.O. Box 122X Hillsboro, Ore.[Signed] Lyle R. Adams '97123
(Water Well Contractor)Contractor's License No. 690 Date March 15, 1979