

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filled with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

STATE ENGINEER

SALEM, OREGON

State Well No.

State Permit No.

275/15E-13

(1) OWNER:

Name Larry Doovers
Address Rt. 2 Box 1402 Madras, Oreg.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
14" Diam. from 0 ft. to 80 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " " "

Bailer test 100 gal./min. with 0 ft. drawdown after 2 hrs.

Artesian flow g.p.m.

Temperature of water 51° Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used cement
Well sealed from land surface to 21 ft.
Diameter of well bore to bottom of seal 18 in.
Diameter of well bore below seal 16 in.
Number of sacks of cement used in well seal 8 sacks
Number of sacks of bentonite used in well seal sacks
Brand name of bentonite
Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake Driller's well number
S.W. 1/4 N.W. 1/4 Section 13 T. 27S R. 15E. W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 35 ft.
Static level 17 ft. below land surface. Date 4-18-74
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 16

Depth drilled 223 ft. Depth of completed well 223 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
top soil - pumice	0'	6'	
hard pan	6'	10'	
gray clay	10'	35'	20'
course sand	35'	36'	20'
gray clay	36'	70'	20'
brown clay	70'	89'	20'
course sand & clay	89'	94'	20'
brown clay	94'	190'	20'
course sand & clay	190'	220'	28'
gray clay	220'	223'	17'

Work started 4-11 1974 Completed 4-18 1974
Date well drilling machine moved off of well 4-23 1974

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] John Cunningham Date 4-24, 1974
(Drilling Machine Operator)

Drilling Machine Operator's License No. 686

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name J.W. Cunningham Well Drilling
(Person, firm or corporation) (Type or print)

Address La Pine, Oreg. 97739

[Signed] John W. Cunningham
(Water Well Contractor)

Contractor's License No. 539 Date 4-24, 1974