

The original and first copy of this report  
are to be filed with theWATER RESOURCES DEPARTMENT,  
SALEM, OREGON 97310  
within 30 days from the date  
of well completion.

## WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 27517E-1cb

State Permit No. G-8375

## (1) OWNER:

Name McQuinn D. & Ramona R. Hall  
Address P.O. Box 166  
Christmas Valley, OR. 97638

## (2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

## (3) TYPE OF WELL:

Rotary ☐ Driven ☐  
Cable ☒ Jetted ☐  
Dug ☐ Bored ☐

## (4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐  
Irrigation ☒ Test Well ☐ Other ☐

## (5) CASING INSTALLED:

Threaded ☐ Welded ☒  
12" Diam. from 0 ft. to 40 ft. Gage 250  
" Diam. from ft. to ft. Gage  
" Diam. from ft. to ft. Gage

## (6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.  
perforations from ft. to ft.  
perforations from ft. to ft.  
perforations from ft. to ft.

## (7) SCREENS:

Well screen installed? ☐ Yes ☒ NoManufacturer's Name  
Type Model No.  
Diam. Slot size Set from ft. to ft.  
Diam. Slot size Set from ft. to ft.

## (8) WELL TESTS:

Drawdown is amount water level is  
lowered below static levelWas a pump test made? ☐ Yes ☒ No If yes, by whom?Yield: gal./min. with ft. drawdown after hrs.  
" " " "Ballor test 950 gal./min. with ft. drawdown after hrs.  
Artesian flow g.p.m.

Temperature of water 62°F Depth artesian flow encountered ft.

## (9) CONSTRUCTION:

Well seal—Material used Cement Grout  
Well sealed from land surface to 40 ft.  
Diameter of well bore to bottom of seal 14 in.  
Diameter of well bore below seal 10 in.  
Number of sacks of cement used in well seal 18 sacks  
How was cement grout placed? POUREDWas a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☐ No Size of gravel:

Gravel placed from ft. to ft.

## (10) LOCATION OF WELL:

County Lake Driller's well number  
NW 1/4 SW 1/4 Section 1 T. 27S R. 17E W.M.  
Bearing and distance from section or subdivision corner

## (11) WATER LEVEL: Completed well.

Depth at which water was first found 35 ft.

Static level 22 ft. below land surface. Date 7-3-79

Artesian pressure lbs. per square inch. Date

## (12) WELL LOG:

Diameter of well below casing 10"

Depth drilled 265 ft. Depth of completed well 265 ft.

Formation: Describe color, texture, grain size and structure of materials;  
and show thickness and nature of each stratum and aquifer penetrated,  
with at least one entry for each change of formation. Report each change in  
position of Static Water Level and indicate principal water-bearing strata.

| MATERIAL       | From | To  | SWL |
|----------------|------|-----|-----|
| Brown top soil | 0    | 2   |     |
| Brown clay     | 2    | 35  |     |
| Blue clay      | 35   | 96  |     |
| Gray clay      | 96   | 225 |     |
| Sand & Clay    | 225  | 265 | 22  |

RECEIVED

JUL 20 1979

WATER RESOURCES DEPT.  
SALEM, OREGONRECEIVED  
JUL 30 1979  
WATER RESOURCES DEPT.  
SALEM, OREGONWork started June 11 1979 Completed July 3 1979Date well drilling machine moved off of well July 5 1979

## Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.  
Materials used and information reported above are true to my  
best knowledge and belief.[Signed] McQuinn D. Hall Date July 18, 1979  
(Drilling Machine Operator)Drilling Machine Operator's License No. owner

## Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is  
true to the best of my knowledge and belief.

Name (Person, firm or corporation) (Type or print)

Address

[Signed] (Water Well Contractor)

Contractor's License No. Date 19