

WATER WELL REPORT
STATE OF OREGON

RECEIVED

MAR 26 1981

State Well No.

275/7E-7a

WATER RESOURCES DEPT
SALEM, OREGON

State Permit No.

(1) OWNER:

Name Golden Rule Farms Inc.
Address P.O. Box
City Christmas Valley State OR.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐
Thermal ☐ Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
14" Diam. from +1 ft. to 98 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.

Air test 1000 gal./min. with drill stem at 120 ft. 1 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement

Well sealed from land surface to 98 ft.

Diameter of well bore to bottom of seal 18 in.

Diameter of well bore below seal 10 in.

Number of sacks of cement used in well seal 87 sacks

How was cement grout placed? Cement was mixed up, pipe run down, along side of pressure grouted in.

Was pump installed? NO Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake Driller's well number
1/4 NE 1/4 Section 7 T. 27S R. 17E W.M.
Tax Lot # Lot Blk Subdivision

Address at well location: 2 1/2 miles west of Christmas Vly., OR.

(11) WATER LEVEL: Completed well.

Depth at which water was first found 118 ft.

Static level 23 ft. below land surface. Date 3/13/81

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

14" to 120" then 10" to 610" then 8" to 740" then 6" to 908"

Depth drilled 908 ft. Depth of completed well 908 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown Clay	0	29	
Green Clay	29	73	
Green Stone	73	198	
Grey Stone	198	382	
Pumice W/B	382	392	
Green Stone	392	440	
Pumice W/B	440	446	
Grey Stone	446	472	
Pumice W/B	472	479	
Grey Stone	479	583	
Grey Clay & Black sand	583	602	
Grey Stone	602	633	
Green Clay & Black sand	633	729	
Green Stone	729	868	
Brown lava rock	868	908	
Broken & W/B		908	

Work started 12/26 1981 Completed 3/13 1981
Date well drilling machine moved off of well 3/13 1981

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Adellut Clark Date 3/16, 1981
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1476

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name McL Search Well Drilling
(Person, firm or corporation) (Type or print)

Address P.O. Box 53 Silverlake, OR.

[Signed] McL Search
(Water Well Contractor)

Contractor's License No. 567 Date 3/22 1981

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690