

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line) SALEM, OREGON

RECEIVED

OCT 1 1974

State Well No. 17s/5W-29ad

STATE ENGINEER Permit No. ~~1111~~

(1) OWNER:

Name George Benson
Address 89381 Fern Drive, Elmira, Oregon 97431

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
4" Diam. from 0 ft. to 494 ft. Gage 1250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "

Bailer test 20 gal./min. with 15 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite
Well sealed from land surface to 23 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal sacks
Number of sacks of bentonite used in well seal 3/4 sacks
Brand name of bentonite Yellowstone
Number of pounds of bentonite per 100 gallons
of water 125 lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lane Driller's well number
SE 1/4 NE 1/4 Section 29 T. 17S R. 5W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 15-20 ft.
Static level 15 ft. below land surface. Date 9-17-74
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing Cased
Depth drilled 494 ft. Depth of completed well 494 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil	0	2	
Clay - brown	2	23	
Clay + gravel - brown	23	35	
Sand - brown - small	35	37	
amount of water			
Sand + gravel - compact	37	41	
brown			
Sand + gravel - brown	41	494	15
water bearing			
Bottom of well in	494		
water bearing sand +			
gravel			

Well was bailed at 40 gal per min
but appeared to be lifting quite a
bit of sand so rate was slowed to
20 gal per min.

Work started 9-13 1974 Completed 9-17 1974

Date well drilling machine moved off of well 9-17 1974

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Well Page Date 9-17, 1974
(Drilling Machine Operator)

Drilling Machine Operator's License No. 159

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Hages & Page Well Drilling
(Person, firm or corporation) (Type or print)

Address 9586 Highway 126, Veneta, Oregon

[Signed] Well Page
(Water Well Contractor)

Contractor's License No. 104 Date 9-17, 1974