

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

RECEIVED

JUN 7 1965 STATE ENGINEER

WATER WELL REPORT

(Please type or print)

G3208

State Well No.

State Permit No.

17/BW-7

LANE 14515

(1) OWNER:

SALEM OREGON

Name George Unser

Address Greenleaf, Oregon

(2) LOCATION OF WELL:

County Lane Driller's well number 241
1/4 S.E. 1/4 Section 7 T.17 South 8 W.W.M.

Bearing and distance from section or subdivision corner

The South 1/2 of the East 1/2 of the South-
East 1/4, Section 7, Township 17 South,
Range 8 West of the Willamette Meridian
All in Lane County, Oregon.

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from Surface ft. to 18 ft. Gage 0.250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

See letter of 6-14-65 Rec'd.

Well seal—Material used in seal bentonite
Depth of seal 12-16 ft. Was a packer used? -0-
Diameter of well bore to bottom of seal 10 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☒ Yes ☐ No Size of gravel: creek
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 61 ft. below land surface Date 6-2
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? driller
Yield: 1800 gal./min. with 5 ft. drawdown after 2 1/2 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 50 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 65 ft. Depth of completed well 65 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Brown top soil with large creek gravel	0	4
Sand & gravel	4	8
Sand, red clay & large creek gravel	8	12
Hard sand stone	12	65

Work started May 29 1965. Completed June 2 1965
Date well drilling machine moved off of well June 3 rd 1965

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Charles Panschow, Rte. 1, Box 192
(Person, firm or corporation) (Type or print)

Address Florence, Oregon

Drilling Machine Operator's License No. 163

[Signed] Mabel Panschow
(Water Well Contractor)

Contractor's License No. 87 Date June 3rd 1965