

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON JUL 3 0 1973

(Please type or print)

(Do not write above this line)

RECEIVED

State Well No.

STATE ENGINEER

SALEM OREGON

State Permit No.

(1) OWNER:

Name Leroy Wiggins
Address Rt 2, Veneta, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
6" O.D. Diam. from 0 ft. to 89 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.
" " " " " " " "

Bailer test 20 gal./min. with 30 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite to 35' clay to 50'
Well sealed from land surface to 50' ft.
Diameter of well bore to bottom of seal 10" to 35' 8" to 50'
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal sacks
Number of sacks of bentonite used in well seal 1 1/2 sacks
Brand name of bentonite Yellowstone
Number of pounds of bentonite per 100 gallons 17.5 lbs./100 gals.
of water
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lane Driller's well number
NE 1/4 NE 1/4 Section 6 T. 18S R. 5W W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 75 ft.
Static level 46 ft. below land surface. Date 7-9-73
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 8 1/2" depth

Depth drilled 89 ft. Depth of completed well 89 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil	0	2 1/2	
Clay - grayish brown	2 1/2	10	
Clay - very sandy brown	10	16	
Clay - gray	16	21	
Clay - brown	21	45	
Clay - grayish brown	45	63	
Clay - gray	63	75	
Clay - sandy - gray	75	83	
Sand + gravel - black	83	89	46
gray or black - water bearing			

Bottom of well in gray 89
or black water bearing
sand + gravel

Work started 7-5 1973 Completed 7-10 1973
Date well drilling machine moved off of well 7-10 1973

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Dele Page Date 7-10, 1973
(Drilling Machine Operator)

Drilling Machine Operator's License No. 159

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Hayes & Page Well Drilling
(Person, firm or corporation) (Type or print)

Address Rt 3 Box 218, Veneta, Oregon

[Signed] Dele Page
(Water Well Contractor)

Contractor's License No. 104 Date 7-10, 1973