

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310

within 30 days from the date
of well completion.

LANE 18395 WATER WELL REPORT

STATE OF OREGON

(Please type or print)

State Well No.

Permit No.

SALEM, OREGON

(1) OWNER:

Name Anthony R. Lienart
Address 86613 Territorial Rd.
Keneta Oregon 97487

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Pile ☒ Jetted ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 11 ft. to 31 ft. Gage 260 W
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Is a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " " " " "

Pump test 5 gal./min. with 100 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 29 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 8 sacks
How was cement grout placed? grouted in
with pump

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lane Driller's well number
1/4 1/4 Section 18 T/18-S R. 5-W W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 106 ft.

Static level 36 ft. below land surface. Date 10/26/80

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6 inch

Depth drilled 250 ft. Depth of completed well 250 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown Soil	1	2	ft.
Gray Clay	2	10	"
Yellow Clay	10	20	"
Blue Clay	20	22	"
Blue Sand Rock M.H.	22	25	"
" " " "	25	100	ft.
Gray Sand Rock	100	132	"
" " " Hard	132	153	"
Gray S.R. Fine	132	168	"
Gray Hard Sand Rock	168	190	"
Gray Hard Sand Rock	190	199	"
" " " "	199	206	"
Gray Fin S.R. with Crevices	206	208	"
Gray Fin S.R.	208	234	"
Gray Hard S.R.	234	245	"
" " " with Crevices	245	250	"

Work started 10/17 1980 Completed 10/27 1980

Date well drilling machine moved off of well 10/27 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Lloyd E. Gardinier Date 10/27, 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 265

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name C.E. Gardinier & Son
(Person, firm or corporation) (Type or print)

Address 1941 Harris St. Eugene, Ore.

[Signed] Lloyd E. Gardinier
(Water Well Contractor)

Contractor's License No. 295 Date 10/27, 1980