

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

RECEIVED

JUL 7 1966

WATER WELL REPORT

18932

State Well No. 18/6w-24G

G-3778

State Permit No.

(1) OWNER:

Name Bill Scharen

Address Rt 1
Veneta, Oregon

(2) LOCATION OF WELL:

County Lane Driller's well number

$\frac{1}{4}$ Section 24 T. 18S R. 6W W.M.

Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐ Rotary ☐ Driven ☐
Irrigation ☒ Test Well ☐ Other ☐ Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(5) TYPE OF WELL:

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
8.800 Diam. from 0 ft. to 37 1/2 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite

Depth of seal 20 ft. Was a packer used? No

Diameter of well bore to bottom of seal 10 in.

Were any loose strata cemented off? ☐ Yes ☒ No Depth _____

Was a drive shoe used? ☐ Yes ☒ No

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

(10) WATER LEVELS:

Static level 6 ft. below land surface Date 6-7-66

Artesian pressure _____ lbs. per square inch Date _____

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

" " " " "

" " " " "

Ball test 40 gal./min. with 60 ft. drawdown after 1 1/2 hrs.

Artesian flow _____ g.p.m. Date _____

Temperature of water _____ Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 95 ft. Depth of completed well 95 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Soil	0	2 1/2
Clay - brown	2	14
Clay - blue - rotten wood	14	32 1/2
Rock - fairly soft gray sandstone	32 1/2	48
Rock - dark gray sandy claystone - water bearing at several levels	48	95
Bottom of well	95	

Work started 6-2 1966 Completed 6-7 1966

Date well drilling machine moved off of well 6-7 1966

(13) PUMP:

Manufacturer's Name Red Jacket

Type: Sub H.P. 2

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Hayes & Page Well Drilling, Oreg. Ltd.
(Person, firm or corporation) (Type or print)

Address Rt 2, Box 218, Veneta, Oregon

Drilling Machine Operator's License No. 159

[Signed] Neil Page
(Water Well Contractor)

Contractor's License No. 104 Date 6-7, 1966