

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

MAR 10 1966

WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date of well completion.

STATE ENGINEER
SALEM OREGON (Please type or print)

State Well No. 18/10w-7
State Permit No. LANE

(1) OWNER: WILLIE J. WORNSTAFF
Name Willey Warren Staff
Address 18th St Swiss Home Oregon

(2) LOCATION OF WELL:

County Lane Driller's well number 1-66
1/4 Section 7 T. 18S R. 10W W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from -1 ft. to 47 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Clay cuttings
Depth of seal 46 ft. Was a packer used? Casing Drilling
Diameter of well bore to bottom of seal 8 in. into Sandstone
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 45 ft. below land surface Date 1/18/66
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdowns made? water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 6 gal./min. with 17 ft. drawdown after 1 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☐ No

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 162 ft. Depth of completed well 162 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Yellow clay	0	20
LT Blue gray sandstone (50 FT)	20	45
LT Blue sandstone Hard	45	104
Dark gray shale Hard	104	162

Work started 12-27-65 Completed 1/18/66

Date well drilling machine moved off of well 1/19/66

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Bonnie Brae Well Drilling
(Person, firm or corporation) (Type or print)

Address R#2 Box 198 Springfield Ore

Drilling Machine Operator's License No. 24

[Signed] R. D. Johnson
(Water Well Contractor)

Contractor's License No. 307 Date 1/18/66