

STATE OF OREGON  
**WATER WELL REPORT**  
 (as required by ORS 537.765)

OCT - 1 1986

WATER RESOURCES DEPT.

LANE

19S/1W-8

019531

SALEM, OREGON

(1) OWNER: Bill Boyd  
 Name Bill Boyd  
 Address 37123 Wheeler Rd.  
 City Pleasant Hill State Or. Zip 97455

Owner's Well Number

(9) LOCATION OF WELL by legal description:

County Lane Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
 Township 19S N or S, Range 1W E or W, WM.  
 Section 8 \_\_\_\_\_  
 Tax Lot \_\_\_\_\_ Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
 Street Address of Well (or nearest address) Zodiac Tavern  
38382 Dexter Rd. Dexter, Or. 97431

(2) TYPE OF WORK:

New Well  Deepen  Recondition  Abandon

(3) DRILL METHOD:

Rotary Air  Rotary Mud  Cable  Other

(4) PROPOSED USE:

Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other

(5) BORE HOLE CONSTRUCTION:

Depth of Completed Well 125 ft.

Special Standards date of approval \_\_\_\_\_

HOLE meter	From	To	SEAL		Amount sacks or pounds
			Material	To	
10"	0	19	Cement	0	16 Sacks
6"	19	125			

How was seal placed? Method  A  B  C  D  E  
 Other

Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_

Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From	To	Gauge	SEAL			
				Steel	Plastic	Welded	Threaded
6"	+1	19	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Location of shoe(s) 19'

(7) PERFORATIONS/SCREENS:

Perforations Method \_\_\_\_\_  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Pumping level	Drill stem at	Time 1/2 hr
15	125	125	1 hr

Temperature of water \_\_\_\_\_ Depth Artesian Flow Found \_\_\_\_\_

Was a water analysis done?  Yes By whom \_\_\_\_\_

Did any strata contain water not suitable for intended use?  Too little  not tested

Salty  Muddy  Odor  Colored  Other

Depth of strata: \_\_\_\_\_

(10) STATIC WATER LEVEL:

23 ft. below land surface. Date 9-13-86

Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WELL LOG:

Ground elevation \_\_\_\_\_

Material	From	To	WB?	SWL
Topsoil	0	1		
Brown Clay	1	6		
Brown Clay, Boulders	6	9		
Brown Clay, Boulders & Gravel	9	12		
Green Sandstone	12	37		
Gray Green Sandstone	37	125	Y	23'

Date started 9-12-86 Completed 9-13-86

(unbonded) Water Well Constructor Certification:

I constructed this well in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed Bob Murphy Date 9-13-86

(bonded) Water Well Constructor Certification:

I accept responsibility for construction of this well and its compliance with all Oregon water well standards. This report is true to the best of my knowledge and belief.

Signed Casey Jones Date 9-13-86

Company John Beck Drilling Co. Co. Job No. \_\_\_\_\_