

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED
LANE 23560
SEP 24 1987

LANE
023560

215/3E-4

(1) OWNER:

Name Michael Nelson Well Number 1
Address P.O. Box 199 WATER RESOURCES DEPT.
City Dillingham State Ak Zip 99576 SALEM, OREGON

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 105' ft.
Explosives used ☐ ☒ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
meter	From	To	Material	From	To	
10"	0	19	Cement	0	19	22 sacks
6"	19	105				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	29	.250	☒	☐	☒	☐
Liner: 4 1/2"	5	105	PVC	☐	☒	☐	☐

Final location of shoe(s) 29'

(7) PERFORATIONS/SCREENS:

☒ Perforations Method SAW
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
45	105	2"	600	1/8"	4 1/2"	☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
40	85	105	1 hr.

Temperature of water _____ Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other not tested

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Lane Latitude _____ Longitude _____
Township 21S N or S, Range 3E E or W, WM.
Section 4 1/4 _____ 1/4 _____
Tax Lot 500 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) High Prairie Rd.
to Nubian Way 2nd house on L. Oakridge

(10) STATIC WATER LEVEL:

20' ft. below land surface. Date 9-4-87
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

From	To	Estimated Flow Rate	SWL
47'	89'	40 gpm	20'

(12) WELL LOG:

Material	From	To	SWL
Topsoil	0	1	
Brown Clay	1	8	
Brown Sandstone	8	11	
Gray Sandstone	11	35	
Brown Gray Green Sandstone	35	41	
Gray Sandstone	41	105	20'

Date started 9-4-87 Completed 9-4-87

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed Robert Murphy WWC Number 1344
Date 9-4-87

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed Casey Jones WWC Number 559
Date 9-4-87



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for Well ID Number

Do not complete if the well already has a Well Identification Number.

RECEIVED

FEB 25 2015

WATER RESOURCES DEPT
SALEM, OREGON

I. OWNER INFORMATION

Current Owner Name (please print): Michael L. Nelson
Mailing Address: P.O. Box 778
City, State, Zip: Oakridge, Oregon 97443
Mail Well ID Tag to: ☒ SAME AS ABOVE ☐ In Care Of (C/O)
Name & Address: _____
City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 21S (North / South) Range: 3E (East / West) Section: 4
Tax Lot: 500 County Lane 1/4 _____ 1/4 _____
GPS Coordinates: _____

Street Address of Well, City: 77499 Bar B-L Ranch Road, Westfir, OR.

If the property had a different street address in the past: High Prairie Rd, Nubian Way
(ie: From "Water Well Report", 09/24/87)

III. GENERAL WELL INFORMATION (Please fill out as completely as possible)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Domestic + irrigation
Date Well Constructed (or property built): 09/24/1987 Total Well Depth: 105 ft. Casing Diameter: 6"
Owner at time the well was constructed (if known): same as above
Other Information: Well tested 40 gpm in 1987, + 50 gpm in 1992'

SUBMITTED BY (please print): Michael L. Nelson
PHONE: (541) 782-2381 EMAIL &/or FAX: _____

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902. Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

2-25-15

Well Log Number:

LANE 23560

Well Identification #:

L-117610