

RECEIVED

LANE 4730 / 9s/12w/22cc / 63753

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

2 LANE 4730

JUN 20 1994

WATER RESOURCES DEPARTMENT (START CARD) #

Instructions for completing this report are on the last page of this form. SALEM, OREGON

(1) OWNER: Well Number 1018 Name Woahink Lake R.V. Resort Address 83570 Hwy 101 S. City Florence State OR Zip 97439

(2) TYPE OF WORK: [X] New Well [ ] Deepening [ ] Alteration (repair/recondition) [ ] Abandonment

(3) DRILL METHOD: [X] Rotary Air [ ] Rotary Mud [ ] Cable [ ] Auger [ ] Other

(4) PROPOSED USE: [ ] Domestic [ ] Community [ ] Industrial [ ] Irrigation [ ] Thermal [ ] Injection [ ] Livestock [ ] Other Test

(5) BORE HOLE CONSTRUCTION: Special Construction approval [ ] Yes [X] No Depth of Completed Well 98 ft. Explosives used [ ] Yes [X] No Type Amount

Table with columns: HOLE Diameter, From, To, SEAL Material, From, To, Sacks or pounds. Row 1: 10", 0', 30', Cement, 0', 30', 9 Sacks. Row 2: 6", 30', 98',

How was seal placed: Method [ ] A [X] B [ ] C [ ] D [ ] E [ ] Other Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 6" 41' 83' .250 [X] [ ] [X] [ ]. Liner: 4" 2' 83' .160 [ ] [X] [ ] [ ]

Final location of shoe(s) None

(7) PERFORATIONS/SCREENS: Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Row 1: 83' 98' .008 [ ] [ ] [ ] [ ] [ ] [ ]

(8) WELL TESTS: Minimum testing time is 1 hour [X] Pump [ ] Bailer [ ] Air [ ] Flowing Artesian Yield gal/min 20+6PM Drawdown 4' Drill stem at Time 1 hr.

Temperature of water 55° Depth Artesian Flow Found Was a water analysis done? [ ] Yes By whom Did any strata contain water not suitable for intended use? [ ] Too little [ ] Salty [ ] Muddy [ ] Odor [ ] Colored [ ] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County Lane Latitude Longitude Township 19S N or S Range 12W E or W. WM. Section 22 SW 1/4 SW 1/4 Tax Lot 101 Lot Block Subdivision Street Address of Well (or nearest address) Same

(10) STATIC WATER LEVEL: 8' ft. below land surface. Date 5/26/94 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found 8.3'

Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 8.3', 98', 20+6PM, 8'

(12) WELL LOG: Ground Elevation

Table with columns: Material, From, To, SWL. Rows: Topsoil (0-1), Brown Sand w/clay (1-5), Brown Sand (5-36), Brown Clay w/sand (36-44), Brown Sand (44-58), Light Brown Sand (58-8.3), Light Brown Sand w/ Gravel (8.3-98)

Date started 5/16/94 Completed 5/26/94

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief. Signed [Signature] WWC Number 1411 Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief. Signed Donald J. Loving WWC Number 751 Date 5/30/94