

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

LANE 4810

RECEIVED  
LANE 4810  
JUL 15 1994

16S/3W/33rd

WATER RESOURCES DEPT. (START CARD) # W69231  
GAL. EM. OREGON

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number \_\_\_\_\_  
Name Bob Harrison  
Address 3720 S. W. 11th, Suite 205  
City Beaverton State OR Zip 97005

(2) TYPE OF WORK  
 New Well  Deepening  Alteration (repair/recondition)  Abandonment

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  Auger  
 Other \_\_\_\_\_

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other Test

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 66 1/2 ft.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
12"	0	19'	Cement	0	19'	11 sacks
8"	19'	66 1/2'				

How was seal placed: Method  A  B  C  D  E  
 Other \_\_\_\_\_  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8"	+1 1/2'	66 1/2'	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 66 1/2'

(7) PERFORATIONS/SCREENS:

From	To	Slot size	Number	Diameter	Material	Tele/pipe size	Casing	Liner
							<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
60	55 1/2'	66 1/2'	1 hr.
Could fluctuate			

Temperature of water 56 Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County Lane Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 16S N or S Range 3W E or W. WM.  
Section 33 SE 1/4 NE 1/4  
Tax Lot 205 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) 33100 VanDuyn Rd.  
Coburg, OR

(10) STATIC WATER LEVEL:  
11 ft. below land surface. Date 7-7-94  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 63'

From	To	Estimated Flow Rate	SWL
63'	66 1/2'	60 gpm	11'

(12) WELL LOG:  
Ground Elevation \_\_\_\_\_

Material	From	To	SWL
Topsoil	0	1'	
Brown clay	1'	6'	
Sand & gravel	6'	66 1/2'	11'

Date started 7-6-94 Completed 7-7-94

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.  
Signed John P. Jones WWC Number 1617  
Date 7-7-94

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.  
Signed Casey L Jones WWC Number 559  
Date 7-7-94



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.oregon.gov/owrd

Application for
Well ID Number

RECEIVED

JAN 20 2022

Do not complete if the well already has a Well Identification Number.

OWRD

I. OWNER INFORMATION

Current Owner Name (please print): Premier RV Park
Mailing Address: 33022 Van Duyn Road
City, State, Zip: Eugene, Oregon, 97408
Mail Well ID to: [X] SAME AS ABOVE [ ] In Care Of (C/O)
Name & Address:
City, State, Zip:

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 16 S (North / South) Range: 3 W (East / West) Section: 33 NE 1/4 of the SE 1/4
Tax Lot (usually last 3-5 numbers of Tax Map #): 100 County Lane
GPS Coordinates: 44.13358826, -123.05030093
Street Address of Well, City: 33022 Van Duyn Road, Eugene
If the property had a different street address in the past: N/A

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Commercial
Date Well Constructed (or property built): 7-7-94 Total Well Depth: 66.5 ft Casing Diameter: 8 inch
Owner at time the well was constructed (if known): Bob Harrison Well Report # (if known): LANE 4810
Other Information:

SUBMITTED BY (please print): Joseph French (EGR and Associates)
PHONE: 541-688-8322 EMAIL &/or FAX: jfrench@egrassoc.com

To send the completed application, you may MAIL it to: Oregon Water Resources Dept. 725 Summer St NE, Suite A, Salem, Oregon 97301.
Or EMAIL the completed PDF form to: Ladeena.K.Ashley@oregon.gov, or FAX it to: (503) 986-0902.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

1-20-22

Well Report Number:

LANE 4810

Well Identification #:

L-145902