

STATE OF OREGON  
**WATER WELL REPORT**  
 (as required by ORS 537.765)

LANE  
 50029

RECEIVED

DEC 11 1995

(START CARD) # 76716

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Name Vallecitos Associates  
 Address 15892 Pasadena Ave., Ste. #220  
 City Tustin State CA Zip 92680

Well Number Y-6

(2) TYPE OF WORK

New Well  Deepening  Alteration (repair/recondition)  Abandonment

(3) DRILL METHOD:

Rotary Air  Rotary Mud  Cable  Auger  
 Other

(4) PROPOSED USE:

Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval  Yes  No Depth of Completed Well 392 ft.  
 Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0'	39'	Cement w/ 4% bentonite	0'	39'	10
6"	39'	392'				

How was seal placed: Method  A  B  C  D  E  
 Other

Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
 Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1'	39'	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: 4"	0	392		<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

Perforations  Screens

Method drill  
 Type \_\_\_\_\_

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
0'	50'		20	3/8"	4"	<input type="checkbox"/>	<input checked="" type="checkbox"/>
90'	173'		5	3/8"	4"	<input type="checkbox"/>	<input checked="" type="checkbox"/>
248'	340'		52	3/8"	4"	<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

well output may fluctuate

Pump  Bailer  Air  Flowing  Artesian

Yield gal/min	Drawdown	Drill stem at	Time
20	380	392'	1 hr.

Temperature of water 51° Depth Artesian Flow Found \_\_\_\_\_  
 Was a water analysis done?  Yes By whom \_\_\_\_\_  
 Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
 Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:

County Lane Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
 Township 18 S N or S Range 3 W E or W. WM. \_\_\_\_\_  
 Section 28 NE 1/4 NE 1/4  
 Tax Lot 1900 Lot 26 Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
 Street Address of Well (or nearest address) south line of lot #26 via Ridgeway Dr

(10) STATIC WATER LEVEL:

12 ft. below land surface. Date 7/6/95  
 Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:

Depth at which water was first found 41

From	To	Estimated Flow Rate	SWL
41'	42'	6 gpm	12
109'	110'	+ 2 gpm	12
223'	224'	+ 7 gpm	12
324'	325'	+ 5 gpm	12

(12) WELL LOG:

Ground Elevation \_\_\_\_\_

Material	From	To	SWL
Topsoil	0	10	
tuff, black-blue, soft	10	42	12
tuff, lt. gray-blue, med.	42	46	12
tuff, dark gray, med. hard	46	75	12
tuff, gray, med-hard	75	173	12
tuff, gray, soft	173	185	12
tuff, lt. gray, soft	185	190	12
tuff, gray, soft-med.	190	205	12
tuff, gray, med-hard	205	270	12
tuff, gray, hard	270	392	12
2 shale traps @ 90', 248'			

Date started 6/29/95 Completed 7/6/95

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number \_\_\_\_\_  
 Date \_\_\_\_\_

Signed \_\_\_\_\_

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Paul Christensen WWC Number 6360 Date 7/24/95