

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

LANE
50109
JAN 22 1996
WATER RESOURCES DEPT. (START CARD) # 66959

Instructions for completing this report are on the last page of this form. SALEM, OREGON

(1) OWNER:

Well Number _____
Name STEVE DIBIRICH
Address 1111 SANTA MONICA BLVD. # 1122
City LOS ANGELES State CA Zip 90025

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 46 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE				SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds	
10"	0	23'	BENTONITE	0	23'	23	
6"	23'	55'					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other UNHYDRATED BENTONITE

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	+2'	43'	250	☒	☐	☒	☐
Liner:	4 1/2"	26'	46'		☐	☒	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

		Method		Type		Material	
		☒ Perforations		<u>SAW-IN</u>			
		☐ Screens					
From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
26'	46'	1/8x5"	60	4 1/2"		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

	Pump	Bailer	☒ Air	Flowing
	Yield gal/min	Drawdown	Drill stem at	Artesian
	30		40"	1 hr.

Temperature of water 55° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County LANE Latitude _____ Longitude _____
Township 16S N or S Range 5E E or W. WM. _____
Section 13 1/4 _____ 1/4 _____
Tax Lot 500 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 56955 MCKENZIE HWY
MC KENZIE BRIDGE, 02974 13

(10) STATIC WATER LEVEL:

24 ft. below land surface. Date 11/15/96
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 41

From	To	Estimated Flow Rate	SWL
41'	55'	30 GPM	24'

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
BROWN CLAY, GRAVEL, & BOULDERS	0	40'	
BOULDERS & GRAVEL	40'	55'	24'

Date started 9/18/95 Completed 1/16/96

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signature Harley C. WWC Number 578
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signature James D. ... WWC Number 126
Date _____