

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

WELL I.D.# L11137

(START CARD) # 096330

(1) OWNER:

Well Number 1502

Name Chuck Phillips
Address 90263 Daisey Ln.
City Elmira State OR Zip 97437

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 130 ft.

Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0'	19'	Bentonite	0'	19'	7 Sacks
6"	19'	130'				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Placed @ 1 sack pr 5 min rate

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	0'	19'	250	☒	☐	☒	☐
Liner: 4"	0'	130'	160	☐	☒	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Elect Saw
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
35'	130'	4x5	90			☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump	☐ Bailer	☒ Air	☐ Flowing
Yield gal/min	Drawdown	Drill stem at	Time
8 Gpm		130'	1 hr.

Temperature of water 57° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Lane Latitude _____ Longitude _____
Township 17S N or S Range 06W E or W. WM.
Section 12 NE 1/4 NE 1/4
Tax Lot 302 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Same

(10) STATIC WATER LEVEL:

18' ft. below land surface. Date 6-3-97
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 58'

From	To	Estimated Flow Rate	SWL
58'	59'	8 Gpm	18'

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Topsoil	0	2	0
Brown Clay	2	8	0
Weathered Sandstone	8	11	0
Gray Sandstone	11	117	18'
Dark Gray Sandstone	117	130	18'

RECEIVED

AUG - 6 1997

RECEIVED

WATER RESOURCES DEPT.
SALEM, OREGON

JUN 30 1997

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 6-3-97 Completed 6-3-97

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed [Signature] WWC Number 1411
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Donald J. [Signature] WWC Number 751
Date 6-4-97