

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

OCT 27 1997

RECEIVED

WELL I.D.# 408859

(START CARD) # 106894

(1) OWNER:

Name DAIRIN GORHAM
Address 4092 HAMPSHIRE, EUGENE
City EUGENE State OR Zip 97404

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☐ No Depth of Completed Well 77' ft.
Explosives used ☐ Yes ☒ No Type — Amount —

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	19	BENTONITE	0	19	8
6"	19	77				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other POURED & TAMPED

Backfill placed from — ft. to — ft. Material —

Gravel placed from — ft. to — ft. Size of gravel —

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+3	77	1/4"	☒	☐	☒	☐
Liner: NONE				☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

From		To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
50	70	1/2" x 1"	360	—	—	—	☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

Pump	Bailer	Air	Flowing
☐	☐	☒	☐ Artesian
Yield gal/min	Drawdown	Drill stem at	Time
20	TOTAL	75'	1 hr.

Temperature of water 50° Depth Artesian Flow Found —

Was a water analysis done? ☐ Yes By whom —

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other —

Depth of strata: —

SALEM, OREGON

(9) LOCATION OF WELL by legal description:

County LANE Latitude — Longitude —
Township 17 S N or S Range 1 E or W. WM.
Section 2 SE 1/4 SE 1/4 RYLEE
Tax Lot 1101 Lot 1 Block — Subdivision COURT
Street Address of Well (or nearest address) VACANT LAND
EAST OF 89800 GREENWOOD DR

(10) STATIC WATER LEVEL:

43 ft. below land surface. Date 8 OCT 97
Artesian pressure — lb. per square inch. Date —

(11) WATER BEARING ZONES:

Depth at which water was first found NOTED @ 45'

From	To	Estimated Flow Rate	SWL
43'	75'	20 GPM	43
		AIR LIFT	

(12) WELL LOG:

Ground Elevation ~ 800'

Material	From	To	SWL
SILTY SAND, DARK BROWN	0	1	—
FINE SILTY SAND (LOAM) BROWN	1	8	—
DENSE SANDY GRAVEL, GREY	8	55	43
SANDY GRAVEL, BROWN	55	57	43
DENSE SANDY GRAVEL, COBBLES	57	75	43
BEDROCK? BASALT	75	77	43

RECEIVED

NOV 26 1997

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 6 OCT 97 Completed 8 OCT 97

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed — Date — WWC Number —

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Walter N White Date 9 OCT 97 WWC Number 638