

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

OCT 27 1997

(START CARD) # 106896

WATER RESOURCES DEPT.

SALEM, OREGON

(1) OWNER:

Well Number 3

Name DARIN GORHAM
Address 4092 HAMPSHIRE
City EUGENE State OR Zip 97404

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☐ No Depth of Completed Well 77 ft.
Explosives used ☐ Yes ☒ No Type Amount

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	18	BENTONITE	0	18	8
6"	18	77				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other POURED & TAMPED

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6	0	77	3/4	☒	☐	☒	☐
Liner: NONE				☐	☐	☐	☐

Final location of shoe(s) NO SHOE (underreamed)

(7) PERFORATIONS/SCREENS:

☒ Perforations Method HOLTE
☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
50	70	1/4" x 1"	360			☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
20	TPA	77	1 hr

Temperature of water 50° Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County LANE Latitude Longitude
Township 17S N or S Range 1 E or W. WM.
Section 2 SE 1/4 SE 1/4 RYLEE
Tax Lot 1101 Lot 3 Block Subdivision COURT
Street Address of Well (or nearest address) 89800 GREENWOOD
DRIVE OFF MCKENZIE HWY

(10) STATIC WATER LEVEL:

43 ft. below land surface. Date 14 OCT
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 43'

From	To	Estimated Flow Rate	SWL
43'	75'	20 GPM	43

(12) WELL LOG:

Ground Elevation APPROX 800'

Material	From	To	SWL
ORGANIC SILTY SAND	0	1	
SILTY SAND	1	9	
SANDY GRAVEL GREY	9	55	43
" " BROWN	55	57	43
" " W/ COBBLES	57	75	43
BEDROCK, BASALT	75	77	43

RECEIVED

NOV 26 1997

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 13 OCT 97 Completed 14 OCT 97

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 638

Signed Walter N White Date 16 OCT 97