

#2

LANE 567

JAN 24 1991

178/2 w/26 db

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

WATER RESOURCES DEPT. SALEM, OREGON

(START CARD) # 17744

(1) OWNER: R-W Well Number: Name GOSSLER FARM NURSERY Address 1200 WEAVER ROAD City SPRINGFIELD State OR Zip 97478

(9) LOCATION OF WELL by legal description: County LANE Latitude Longitude Township 17 S Nor S. Range 02 W E or W. WM. Section 26 NW 1/4 SE 1/4 Tax Lot 900 Lot Block Subdivision Street Address of Well (or nearest address) 1200 WEAVER ROAD SPRINGFIELD, OR 97478

(2) TYPE OF WORK: [X] New Well [] Deepen [] Recondition [] Abandon

(3) DRILL METHOD: [] Rotary Air [] Rotary Mud [X] Cable [] Other

(4) PROPOSED USE: [] Domestic [] Community [] Industrial [X] Irrigation [] Thermal [] Injection [] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval Yes No Depth of Completed Well 80 ft. Explosives used [] [X] Type Amount

Table with columns: HOLE Diameter, From, To; SEAL Material, From, To; Amount sacks or pounds. Row 1: 12", 0, 18', CEMENT, 0, 18', 18 SACKS. Row 2: 8", 18', 80', , , ,

How was seal placed: Method [] A [] B [X] C [] D [] E [] Other Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 8", +1, 80', .250, [X], [], [X], []. Liner: [], [], [], []

(7) PERFORATIONS/SCREENS: [X] Perforations Method MILLS KNIFE [] Screens Type Material

Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Row 1: 20', 80', 3/8X2, 250, 8", , [X], []

(8) WELL TESTS: Minimum testing time is 1 hour [] Pump [X] Bailer [] Air [] Flowing Artesian Yield gal/min 60 Drawdown 10' Drill stem at Time 1 hr.

Temperature of water 52° Depth Artesian Flow Found Was a water analysis done? [] Yes By whom Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other Depth of strata:

(10) STATIC WATER LEVEL: 10 ft. below land surface. Date 1/9/91 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found 20'. Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 20', 80', 300 GPM, 10'

(12) WELL LOG: Ground elevation. Table with columns: Material, From, To, SWL. TOP SOIL 0' 5' SANDY GRAVEL 5' 12' CLAY & SAND MIXED 12' 22' SANDY GRAVEL & CLAY MIXED 22' 64' 10' SANDY GRAVEL & SMALL COBBLES 64' 80' 10'

Date started 12/17/90 Completed 1/9/91

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Signed _____ WWC Number _____ Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. Signed _____ WWC Number 126 Date 1/16/91