

RECEIVED

MAY 05 1999

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 35266
START CARD # 120084

Instructions for completing this report are on the last page of this form.

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER: Well Number _____
Name OR-AZ Holdings
Address 6220 East Thomas Rd. #202
City Scottsdale State AZ Zip 85251

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 412 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL				
Diameter	From	To	Material	From	To	Sacks or pounds	
10"	0	48	cement	0	48	15 sacks	
6"	48	412					

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+2	48	250	☒	☐	☒	☐
Liner: 4 1/2"	2	412	pvc	☐	☒	☒	☐

Final location of shoe(s) 48 ft.

(7) PERFORATIONS/SCREENS:

☒ Perforations Method saw
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
232	252	2"	200	1/8"	4 1/2"	☐	☒
272	292	2"	200	1/8"	4 1/2"	☐	☒
352	372	2"	200	1/8"	4 1/2"	☐	☒
392	412	2"	200	1/8"	4 1/2"	☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
20	306	412	1 hr.

Temperature of water 54 Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Lane Latitude _____ Longitude _____
Township 21S N or S Range 3E E or W. WM.
Section 4 NE 1/4 SE 1/4
Tax Lot 700 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 77406 High Prairie Rd., Oakridge, OR

(10) STATIC WATER LEVEL:

106 ft. below land surface. Date 3-22-99
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 136 ft.

From	To	Estimated Flow Rate	SWL
136	137	6	106
246	247	14	106

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Red clay	0	35	
blue red green sandstone	35	43	
blue basalt	43	67	
brown blue sandstone	67	253	106
blue green sandstone	253	354	
gray green sandstone	354	412	

Date started 3-18-99 Completed 3-22-99

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed [Signature] WWC Number 1617 Date 3-22-99

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 1541 Date 3-22-99